

Cross-Diffusion Waves resulting from multiscale, multiphysics

Instabilitiesinstabilities: Application to earthquakes

Klaus Regenauer-Lieb¹, Manman Hu², Christoph Schrank³, Xiao Chen¹, Santiago Peña Clavijo¹, Ulrich Kelka⁴, Ali Karrech⁵, Oliver Gaede³, Tomasz Blach¹, Hamid Roshan¹, Antoine B. Jacquey⁶, Piotr Szymczak⁷, and Qingpei Sun²

¹School of Minerals and Energy Resources Engineering, UNSW, Sydney, NSW 2052 Australia

²Department of Civil Engineering, The University of Hong Kong, Hong Kong

³Science and Engineering Faculty, Queensland University of Technology, Brisbane, QLD, 4001, Australia

⁴CSIRO, Deep Earth Imaging FSP, Kensington, Australia

⁵School of Engineering, University of Western Australia, Crawley, WA 6009, Australia

⁶Department of Civil and Environmental Engineering, Massachusetts Institute of Technology, Cambridge, MA, USA

⁷Institute of Theoretical Physics, Faculty of Physics, University of Warsaw, Poland

Correspondence: Klaus Regenauer-Lieb (regenau@gmail.com)

Abstract. Theoretical approaches to earthquake instabilities propose shear-dominated ~~instabilities as a source mechanism~~source mechanisms. Here we take a fresh look at the role of possible volumetric instabilities preceding a shear instability. We investigate the phenomena that may prepare earthquake instabilities using the coupling of Thermo-Hydro-Mechano-Chemical reaction-diffusion equations in a THMC diffusion matrix. We show that the off-diagonal cross-diffusivities can give rise to a new class of waves known as cross-diffusion or quasi-soliton waves. Their unique property is that for critical conditions cross-diffusion waves can funnel wave energy into a ~~quasi-stationary~~stationary wave focus from large to small-scale. We show that the rich solution space of the reaction-cross-diffusion approach to earthquake instabilities can recover classical Turing instabilities (periodic in space instabilities), Hopf bifurcations (spring-slider like earthquake models) and a new class of quasi-soliton waves. Only the quasi-soliton waves can lead to extreme focussing of the wave energy into short wavelength instabilities of short duration. The equivalent extreme event in ocean waves and optical fibres leads to the appearance of 'rogue waves' and high energy pulses of light in ~~lasers~~photonics. In the context of hydromechanical coupling, a rogue wave would appear as a sudden fluid pressure spike on the future fault plane. ~~This is~~These are here interpreted as a trigger for the ultimate (shear) seismic moment release.

1 Introduction

Part 1 (Regenauer-Lieb et al., 2021) introduced a (geo-)wave mechanics, physics-based formulation for deciphering patterns of multiphase material instabilities from the molecular scale to any larger scale. Although the paper is formulated for earth sciences the approach constitutes a generic theory for any material and therefore lacks experimental evidence. In ~~the second part~~this paper (Part 2) we investigate whether the approach can be applied to a real world geological system.

The challenge to come up with an approach that defines new concepts for the application of multi-scale non-equilibrium thermodynamics to earth system science was originally posed in the 'Patterns in our Planet' conference in Victor Harbor, South Australia in May 2008 (Ord et al., 2010). Patterns in our planet Patterns in geological systems are thought to encode information on reaction-diffusion processes repeating themselves over multiple scales such that a magnified view of the structure looks like a copy of the structure itself (called self-affinity or self-similarity) (Hobbs et al., 2011) if no affine transformation is required (Hobbs et al., 2011; Hobbs and Ord, 2015; Aifantis, 2021). The connection between these patterns as dissipative structures of reaction-diffusion systems (Ball, 2012) and their role in thermodynamic far-from-equilibrium systems was originally described by Prigogine and co-workers (Kondepudi and Prigogine, 1998). An application of self-diffusing reaction-diffusion equations to mineralising systems has been proposed recently (Oberst et al., 2018). This contribution investigates geological applications of the possible relation to the reaction-diffusion-reaction-cross-diffusion wave phenomenon due to the new addition of the cross-diffusion term proposed in part Part 1 (Regenauer-Lieb et al., 2021). In this contribution we will show why the addition of the cross-diffusion term may be an important element for the earthquake source mechanism.

Along the same vein, the paper also attempts to give a somewhat simpler description of the theory from a chemical perspective putting part mesoscale perspective, putting Part 1 into context with other more familiar theories as well as recent further developments thereof. the context of nonlocal processes summarised in recent developments on size-dependent continuum mechanics approaches (Shaar and Ghavanloo, 2021). We identify that these ideas can be amalgamated with new concepts in physics and mathematics on nonlocal reaction (Rubinstein and Sternberg, 1992) and diffusion (Amdreo-Valle et al., 2010) processes. Such formulations provides a more rigorous framework for the consideration of processes that happen in-between scales. These processes are loosely called the "mesoscale" without precise definition.

In continuum mechanics nonlocal processes are found to be important for introducing internal length-scales for localisation phenomena (Aifantis, 2021). We emphasize here that consideration of the nonlocal cross-diffusion terms is particularly important to link the feedbacks between different self-diffusion length scales which are normally not considered in the coarse graining homogenisation approaches discussed later.

In order to explain the physics of nonlocal diffusion processes, consider an assembly of solid and fluid particles/molecules in a fully saturated porous medium. The particles are subject to a pressure exerted by the solid matrix and the pressure of the pore fluid. If we further consider a chemical dissolution-precipitation process as an example the concentration of solid and fluid particles/molecules depend on their position in space and the gradients of their concentrations which an equation of state approach can be interpreted as fluid pressure. Cross-diffusion describes the nonlocal effect of the convolution of the concentrations of solid and fluid particles. This convolution occurs because the release of a fluid particle relies on the dissolution of a solid particle and the growth of a solid particle needs the precipitation of a fluid particle. The probability distribution to jump from one location to another is then defined as the nonlocal diffusion. In the context of Part 1 these mesoscale or nonlocal jump conditions may under certain scenarios be incompatible with the large scale thermodynamic forces and violate the equilibrium condition. Such violation then necessarily leads to the nucleation of acceleration waves radiating the local energetic incompatibilities into the far field. In the discussed example of dissolution-precipitation reactions a molecular reaction may therefore radiate solid and fluid pressure pulses into the far field and act as a perturbation to the coupled nonlocal




Figure 1. Earthquake frequency-magnitude histogram prepared from the Global Instrumental Earthquake Catalogue, Version 7.0 - released on 9/4/2020 by the ISC-GEM (Di Giacomo et al., 2018; Storchak et al., 2015, 2013). Global quakes have a fractal power law relationship of $\log(\text{Number of Earthquakes}) = 10.23 + 1.06 (\text{Magnitude})$ with an $R^2 = 0.98$. The log-log relationship between numbers of earthquakes and their moment magnitude on all sizes of completeness of the catalogue suggests a simple underlying reason why the physics of the very small influences the physics of the very large in a multifractal cascade of instabilities. Sethna et al. (2001) postulates that this can be explained by the existence of a critical thermodynamics force above which an earthquake starts to slip. Accordingly, plate motions self-regulate (Sornette and Pisarenko, 2003) to be exactly at this critical point for potential failure at all scales.

55 [phenomena at the next scale up thus triggering the full cascade of THMC nonlocal reaction-diffusion processes and leading to a multifractal cascade of instabilities \(Turiel et al., 2006; Koronovsky et al., 2019\).](#)

A prime example of how the physics of the very small appears to influence the physics of the very large is the earthquake instability ([Sornette, 1999; Crampin and Gao, 2015](#))([Sornette, 1999; Crampin and Gao, 2013](#)). We therefore use earthquakes as a topic to discuss the roots of [self-similarity underpinning the log-log frequency-magnitude relationship self-affinity underpinning the log-frequency log-magnitude relationship \(Fig. 1\)](#) and many other similar relationships in nature ([examples are shown in Fig. 41 of Part 1 \(Regenauer-Lieb et al., 2021\)](#)). To simplify the equations and address a frequently overlooked deformation mode we use the Helmholtz decomposition presented in [part Part 1 \(Regenauer-Lieb et al., 2021\)](#) and only discuss examples for dissipative pressure (P) waves. The rich dynamics of superposing dissipative pressure (P)- and shear (S)- waves will be subject of future research. [For simplifying the discussion we also focus on just considering HM coupling and refer to Part 1 for the generalised THMC formulation.](#)

65 Working Hypothesis: This paper develops the hypothesis that [patterns-in-our-planet-geological patterns](#) encode information of dissipative structures in the form of standing [or travelling dissipative](#) waves that can appear [when-a-with \(Berenstein and Beta, 2012\)](#) [or without](#) cross-diffusion [term-is-added-to-reaction-diffusion-equations \(Berenstein and Beta, 2012\)](#) [terms \(Regenauer-Lieb et al., 2013a; V](#)

. We develop a continuation of a solid mechanical cross-diffusion formulation in which slow damage waves (Hu et al., 2020) have been identified as a precursor phenomenon to macroscopic failure of porous materials under load. The failure-Diffusion waves prepare a material for failure as they lead to internal material damage. Developing detection methods of these newly predicted slow damage waves may point to new avenues of forecasting material failure. Additionally, the failure pattern induced by these waves imprints can imprint a characteristic bar-code like signature around the main failure zone. If it is possible to decipher these patterns as frozen-in stationary states of reaction-diffusion systems, the approach may provide new avenues to investigate one of the most difficult unsolved problems in earth sciences through direct geological observations.

70 Complex-Other avenues for detecting these waves could be through laboratory experiments. Unfortunately, complex earth-/material dynamic reaction-diffusion processes occur under extreme temperature and pressure conditions and on time-scales inaccessible to the direct human observer (Kohlstedt and Holtzman, 2009). Therefore, reliable empirical experimental engineering approaches for estimating the risk of failure of Earth-earth materials under both engineering and plate tectonic loads are missing (Grigoli et al., 2018). A particular challenge is to replicate nature's pattern forming, self-organised critical conditions
80 (Fig. 1) at micro-scale in the lab, as the earth's long-range feedbacks are missing.

We-To solve this problem we use a thermodynamic-based continuum mechanics approach where we consider conservation of mass, conservation of linear momentum, conservation of angular momentum, conservation of energy, and the second law of thermodynamics as the basic set of coupled partial differential equations (*pde's*). These equations form the basis of deterministic continuum mechanics while the strong form of the second law is used as a bridge between statistical mechanics
85 and continuum approaches (Ostoja-Starzewski, 2008). In this respect the thermal (T) *pde* has a special role as it is tied to the entropy evolution and thereby encapsulates the uncertainty quantification for time-dependent processes through the fluctuation theorem (Evans and Searle, 2002). For a complete approach, we must look for a mathematical description that comprises all four coupled partial differential equations in a holistic way including the important uncertainty quantification.

The wave-mechanics approach offers just this opportunity as it encompasses all conservation laws including the uncertainty
90 relationship. The wave mechanics approach of part-Part 1 (Regenauer-Lieb et al., 2021) offers in particular gives, in particular, a fundamental physics-based first guess to investigate these critical domains that are not directly accessible. We thereby identify critical conditions for many important earth science problems such as the physics of earthquakes, extraction of geothermal energy, safety of nuclear waste disposal, reservoir engineering for oil and gas, the formation of mineral deposits, induced seismicity, natural hazards, groundwater management, and CO_2 -sequestration and utilization. In sections to come, we will
95 formulate a simple nonlocal reaction-diffusion formulation for hydromechanical (HM) coupling, illustrate the potential first application of the theory and depict its relation to other similar approaches in different disciplines.

2 THMC length and time scales Coarse graining techniques in the light of the earthquake problem

The decoupling of dynamic processes on vastly different length and time scales is one of the most powerful methods of upscaling techniques. The objective, thereby, is to reduce the level of complexity by coarse-graining (Sethna, 2006; Hanasoge et al.,
100 2017) a complex thermodynamic system to a larger system, such that the dynamics of the lower scale can be homogenized

into an effective material property for the larger scale (see Fig. 2). The dynamical system maps onto itself in a **self-similar self-affine** fashion so that the dynamic behaviour under external loads is the same irrespective of the scale considered. This so-called coarse-graining approach leads to time-evolution of the thermodynamically averaged larger systems that have significantly simpler time-evolution equations. The dynamic processes at lower scale are assumed to have relaxed to a quasi-steady state (local thermodynamic equilibrium) and contribute to the larger system through what is described in statistical physics by an order parameter characterising the scale-invariant free energy of the statistical volume considered (Sethna, 1992). This situation can lead to a cascade-like hierarchy of singularities described by a series of local power laws.

The system would then be expected to feature a multiscale combination of local power laws of Thermo-Hydro-Mechano-Chemical (THMC) reaction-diffusion equations leading to multifractal distributions where different scales have different fractal properties (Stanley and Meakin, 1988). This multifractality relies on a random multiplicative process of each underlying physics and a coupling of the critical point phenomena into the universality relationships of the THMC-coupled processes. The combination of a thermally activated rupture with a long memory stress relaxation was proposed as a possible mechanism to explain the multifractal scaling of the Californian earthquake catalogue (Sornette and Ouillon, 2005). The multifractality hypothesis of the Californian dataset has been reinvestigated in a more recent multiscale analysis of the micro-, meso- and macro-scale subsequences showing that the macro-scale spectrum indeed has the strongest multifractality of the three scales, thus strongly supporting the hierarchy of scales (Fan and Lin, 2017). This finding calls for a true multiscale formulation for earthquake physics, where the largest scale geodynamic driver is coupled to the smallest scale singularity in a multiphysics hierarchical cascade of instabilities. In sections to come we will illustrate how the nonlocal cross-diffusion terms provide the missing glue between the scales. We will discuss analytical solution showing that cross-diffusion can focus wave energy from the large scale to small scales in short sharp instabilities first discovered in hydrodynamics (Peregrine, 1983).

When extrapolating the findings from the Californian dataset to the global earthquake dataset we infer that the multifractal, so-called singularity spectrum (Turiel et al., 2006) contains most -but unfortunately not all- information about the physics of earthquakes (see Fig. 1). (Koronovsky et al., 2019). The continuous spectrum of multiscale exponents contained in the global singularity spectrum suggests that there is a mechanism that is capable of coupling the various THMC reaction-diffusion equations. Individual coupling mechanisms have been discussed such as a creep activation mechanism (Sornette and Ouillon, 2005), shear heating (Ogawa, 1987; Regenauer-Lieb and Yuen, 1998; Braeck and Podladchikov, 2007), thermally induced fluid pressurization (Vardoulakis, 2001; Rice, 2006) and a mixed process between frictional slip failure and the shear fracture of intact rock (Ohnaka, 2003). A generic physics-based formulation for investigating multifractality of the earthquake mechanism that does not single out individual processes is still lacking. ~~The current work attempts to develop~~ Part 1 (Regenauer-Lieb et al., 2021) has presented such a generic framework and here we illustrate its application to the hydromechanically coupled reaction-cross-diffusion which may be used as a simple first approach to earthquake instabilities (Crampin and Gao, 2015).

A possible candidate for cross-scale communication, could be the propagation of cross-diffusional waves which can tie several or all THMC reaction-processes together in a convolution operation as discussed in Part 1 (Regenauer-Lieb et al., 2021). The time-domain convolution operation of THMC waves can be seen in the frequency-domain as a filter for the dominant




Figure 2. Coarse graining approaches in continuum and fluid dynamics. The microscale has the richest information and highest degrees of freedom. Coarse graining reduces the complex dynamics to time-evolution equations with a less detailed level of description. In the continuum scale only reduced variables are retained. In the case of the Navier-Stokes equation for fluid dynamics, these are pressure and velocity. The wave mechanics approach presented here is a meso-scale approach that opens the path for an analytical reduction of variables rather than a computational coarse-graining method based on averages. ~~This enables~~ Examples for three different methods are shown. The top row illustrates the derivation-simulation of a solid body with a Particle Flow Code (PFC modified after Durrleman et al. (2006)) and the continuum damage model (modified after Lyakhovsky et al. (2015). The Arrhenius dependent temperature response is considered in other continuum damage formulations (Hu et al., 2017). The middle row shows a dissipative particle dynamics approach (modified after Español and Warren (2017)) and the bottom row a Lattice Boltzmann homogenisation technique (modified after Fitzgerald et al. (2019)). Our approach replaces the explicit simulations by considering the meso-scale processes through consideration of nonlocal effects of cross-diffusion. These effects enrich the upscaling of physics-based macro-scale constitutive equations for-at the continuum scale. This-The approach is complementary to the numerical coarse-graining techniques shown in this figure.

earthquake coupling mechanism, sharpening or smoothing certain ~~cross-diffusion waves~~ waves controlled by cross-diffusion. In this sense, the earthquake physics problem may, therefore, be condensed to the problem of how to couple instabilities across scale such that a dominant wave can lead to a ~~self-similar self-affine~~ macroscale instability mechanism which we propose to be an extreme form of a sharpening filter in the language of signal processing. In the physics field, this phenomenon is known
 140 as a rogue-wave (~~Eberhard et al., 2017b~~)(Eberhard et al., 2017a). To verify or falsify the rogue-wave hypothesis as a potential earthquake trigger mechanism, we need to discuss the interplay of the vastly different time- and length- scales of the THMC reaction-diffusion processes.

The characteristic time and length scales of the thermodynamic THMC processes can be evaluated by calculating the relaxation time of a random perturbation from the THMC reaction term ~~R_i, R_i'~~ . Please refer to Table 1 in Part 1 (Regenauer-Lieb et al., 2021)
 145 for a definition of the THMC reaction terms. Characteristic time- and length- scales emerge from quasi-steady-state (time-independent) solutions of the diffusive (relaxation) response of the reaction-diffusion system characterised by the equation

$$\frac{\partial C_i}{\partial t} = \nabla \cdot (\zeta_i' \nabla C_i) + R_i', \quad (1)$$

where C_i stands for the diffusing species/processes (e.g. temperature, fluid or mechanical pressure, chemical species) and ζ'
 150 for the respective diffusivity with the subscript i denoting the THMC processes. Linearising the diffusion equation ~~to first order~~ we obtain

$$\frac{\partial C_i}{\partial t} = \zeta_i \nabla^2 C_i + R_i. \quad (2)$$

The time scale or the relaxation process is now entirely characterised by the self-diffusion ~~constants~~ coefficients $\zeta_{T,H,M,C}$ and the reaction ~~rate constants~~ rates R_i . Please refer to the Part 1 (Regenauer-Lieb et al., 2021) for a definition of self-diffusion
 155 and cross-diffusion coefficients.

2.1 Self-Diffusion length/time scale

~~For a discussion of the length scale encountered through the diffusion of a local reaction source term of the THMC process (i.e. local heat release, fluid or mechanical pressure source term, chemical reaction) we treat the concentration C_0 released by the reaction at t_0 as an initial condition and set $R_i = 0$ for the remainder of the process $t > 0$. We use this instantaneous source as a point source in an infinite plane. This linear partial differential equation requires one initial condition (local release of concentration C_0 as a point source due to the reaction at $x = 0$) and two boundary conditions for solution. The boundary conditions are $C_i = 0$ at plus and minus infinity. Mass (momentum, energy and entropy) balance requires that at any time the concentration (mechanical/fluid pressure, heat content) is:-~~
 160

$$C_0 = \int_{-\infty}^{\infty} C_i dx.$$

165 If we assume that the initial and boundary conditions are unchanged by a scale change, as required by the coarse graining assumption, the [For the benefit of the reader wishing to recap the](#) well-known solution method is obtained by scaling the equation with a characteristic diffusional length scale. This diffusion length scale defines the characteristic length scale of propagation of the information from a local perturbation, e.g. for chemistry an instantaneous point source in the concentration of the diffusing species being released at the origin $x = 0$ at $t = 0$ in a given time t_d . For fluid flow and mechanics this would
 170 be a local source of fluid or mechanical pressure, and for temperature this perturbation would be a local heat source. Any scale that is significantly larger than the diffusional length scale is considered to be unaffected by the diffusion front for a given diffusion time t_d . We will later on reinterpret the diffusion length as an uncertainty measure. The characteristic diffusion length scale is:-

$$L_d = \sqrt{4\zeta_i t_d}$$

175 which is used as part of the scaling method for solving Eq. 2 described in standard textbooks e.g. (Crank, 1975). Using the previously described initial and boundary conditions, the diffusion front spreads radially in a concentration profile-

$$C_i(x, t) = \frac{C_0}{L_d \sqrt{\pi}} \exp - \left(\frac{x}{L_d} \right)^2$$

Illustration of the diffusion length scale using the example of a point source pulse of concentration applied as an initial condition in a plane at $t = 0$ with $C_0 = 1$. An arbitrary diffusivity of $1 \text{ m}^2 \text{ s}^{-1}$ is selected. Three time snapshots are shown at (0.01, 0.06,
 180 and 1 s) showing that the normalised concentration reduces while the pulse broadens as a Gaussian wavelet (Gaussian kernel in the language of image processing) with a wavelength characterised by the diffusion length scale L_d . The broadening of the wavelength is defined by twice the diffusion length L_d due to the bi-directional diffusion process. The diffusion length scale describes the wavelength at exactly the same fraction (here $\frac{1}{e} \approx 0.37$) of the maximum magnitude of concentration at a given time step.

185 The solution shown in Fig. ?? illustrates the fast decrease of the amplitude with increasing time coupled with an increase in L_d . The normalisation over $\frac{1}{L_d \sqrt{\pi}}$ in Eq. ?? ensures that the area under the curve always remains the same and satisfies Eq. ?? thus defining a Gaussian scale space. The Gaussian probability density function (here called a Gaussian wavelet) is often used in probability theory where the diffusion length is related to [facts about the topic of reaction-self-diffusion waves including their astonishing behaviour of revealing THMC material properties through their propagation velocity, we summarize in the](#)

190 standard deviation, its square to the variance and the function centroid to the mean. **Self Diffusion – Diffusivity** [m^2/s] ——— **Process time** [s] ——— **Diffusion Length** [m]
 $\zeta_T \ 10^{-6} 10^{12} \ 10^3 \zeta_H \ 10^{-5} \ 10^{-1} 10^2 \ 6 \times 10^{-2} \ 6 \times 10^0 \zeta_M \ \text{all all} \ \text{all} \ \zeta_C$
 $10^{-19} \ 10^{-15} \ 10^{12} \ 6 \times 10^{-4} \ 6 \times 10^{-2}$ Typical diffusion length scales for geological THMC processes (Regenauer-Lieb et al., 2013a). Note, the mechanical diffusion length scale can range over all scales. As an example the visco-elastic diffusion length scale for elasto-dynamic earthquake events is very short. However, prior to the catastrophic event stress diffusion can range over all
 195 scales and can couple all processes through elasto-visco-plastic creep processes.

2.1 Reaction-Diffusion length/time scales

So far, we have discussed a point source reaction as an initial condition at time t_0 [appendix an example of an autocatalytic reaction](#) and $x = 0$ with no additional time-scale other than the self-diffusion process afterwards. This leads to a decaying and broadening diffusion wavelet (Fig. ??). When considering an active source term, the solution turns into a propagating wavefront which was first discovered in 1906 by Robert Luther. An English translation of the original article appeared in the Journal of Chemical Education (Luther, 1987). The same phenomenon was rediscovered 30 years later and is now known as Fisher or Fisher-Kolmogorov equation (Adomian, 1995). Fisher originally discussed the reaction-diffusion equation to calculate the propagation of a mutant virus in an infinite domain (Fisher, 1937). Following Showalter and Tyson (1987) we recast Fisher's arguments for calculating the minimum speed of the propagation of the mutant gene at long time scales into a discussion of a propagation of a chemical reaction front. For the example discussed in Fig. ?? consider the following autocatalytic chemical reaction:-



where A is the reactant and C is the catalyst, n is the autocatalysis order with the number of reaction steps with $n = 1$ being the elementary reaction (Valero and Moyano, 2017). The square bracket indicates the number of moles. The reaction rate is $R_c = k[C] = \frac{d[C]}{dt}$ with k being the first-order reaction rate here defined with respect to the reaction product rather than the reactant, hence the positive sign. This reaction depends on the concentration of only one reactant. The system may have other reactants, but these are not influencing the rate of the reaction. In chemistry this situation is known as a first-order reaction. As we are interested in a moving reaction front, we may consider just the initial response of the reaction. Thus instead of the typical sigmoid solution, which considers the depletion of A in the course of the reaction, we may consider a non-physical infinite pool, where A is not depleted by the reaction, and integrate the first-order reaction by an exponential growth of the reaction product, with

$$[C(t)] \equiv [C_0] \exp(kt).$$

The minimum velocity of the propagating reaction-diffusion wavelet that is triggered by an initial delta-function reaction at time t_0 can be evaluated by extending the solution in Eq. ?? to consider the exponential reaction product and obtain:-

$$[C(x, t)] = \frac{[C_0] \exp(kt)}{L_d \sqrt{\pi}} \exp - \left(\frac{x}{L_d} \right)^2.$$

Separating variables -

$$[dC] = \frac{\partial[C]}{dx} + \frac{\partial[C]}{dt},$$

and substituting the separation into Eq. ?? we obtain an ordinary differential equation (ode)-

$$\frac{dx}{dt} = \frac{2k\zeta t}{x} + \frac{x}{2t} - \frac{\zeta}{x},$$

225 where ζ is the diffusivity. This shows that for large t and large x the last two terms of Eq. ?? vanish, and a constant wavefront velocity is expected to approach

$$v = \sqrt{4\zeta k},$$

230 which is a lower bound of the steady front velocity at large t . We can use this speed as a quasi-steady-state solution of the composition wave triggered by the reaction and obtain a quasi-steady state diffusion length scale of $L_d = \frac{\zeta}{v}$ that propagates with the wavefront. This diffusion front is the only information, that is carried by the wave at long length and time scale, and highlights one of the fundamental differences between reaction-diffusion waves and elastic waves. Reaction-diffusion waves quickly diffuse information of the initial condition and at long time scales are only characterised by the competition between reaction rates and diffusion rates. Pure elastic waves, when propagating without damping, diffraction and scattering, carry the full source information through their entire travel path.

235 Illustration of the propagating wavefront of the Fisher-Kolmogorov equation which is Eq. ?? with a nonlinear source term $R_i = k_i C_i (1 - C_i)$. Kolmogorov et al. (1937) showed that any initial concentration vanishes for large x and evolves to a travelling wave solution with a minimal velocity $v = \sqrt{4\zeta_i k_i}$. The reaction-diffusion exhibits a bistable equilibrium. One stable equilibrium is achieved when the initial concentration is below the activation of a wave and the system is resting and the other is the travelling wave solution with a minimal velocity v . We show here the non-dimensional solution for the example of a *tanh* 240 initial condition (black curve) which quickly converges to a travelling waveform with a non-dimensional speed of 2. Various solution techniques exist. A convenient method is to turn the partial differential equation (Eq. 2) into an ordinary differential equation by using Chebyshev polynomials (Towers and Jovanoski, 2008). The above example of a chemical autocatalytic reaction illustrates the key features of reaction-diffusion equations in many scientific disciplines and applies to all C_i 's and R_i 's of THMC systems. Adding an active non-linear source term (e.g. $R_i = k_i C_i (1 - C_i)$ for the Fisher-Kolmogorov equation) 245 into the diffusion equation can lead to the interesting phenomenon of the generation of a self-oscillatory excitation wave, where after Fisher's work on the topic progress was mainly made in the Russian literature triggered by the seminal work of Kolmogorov et al. (1937) discussed in Fig.??.

In Russian literature, the term "autowave" was introduced (Ostrovskii, 2015). The autowave phenomenon is well-studied for understanding the electrical nerve impulse that leads to contraction of the heart muscle (Antonioletti et al., 2017). However, 250 it constitutes a fundamental class of waves encountered in all reaction-diffusion systems in physics, biology, and chemistry (Vasil'ev, 1979). The principal difference to classical wave equations that are based on hyperbolic differential equations, is that the autowave phenomenon arises from a non-linear source term in parabolic equations. When adding a cross-diffusion term autowaves can turn into standing waves (Berenstein and Beta, 2012) having completely different properties to classical standing wave solitons. This difference defines a new class of dissipative waves which, according to Tsyganov and Biktashev (2014) 255 , presents an entirely different "world" to the waves encountered in integrable conservative systems such as the elastic-wave phenomenon. This phenomenon will be discussed further in the section on cross-diffusion waveforms where we will discuss the most important property for nucleation of earthquakes. This is the potential of multiscale funnelling of wave energy from

the environment into a localised standing wave. Before going there, we continue with a discussion of the reaction-diffusion equation without the cross-diffusion term in order to systematically describe its basic characteristics.

260 its role in the nucleation of reaction-self-diffusion waves. The reader familiar with the literature on reaction-diffusion time-scales of a single reaction-diffusion equation can be expressed by a generalization of the Damköhler number for chemical reaction-diffusion processes to all THMC couplings. The Damköhler number describes the ratio of the diffusion over the reaction time or the equivalent ratio of the reaction over the considered diffusion rate. This ratio now defines a new time-scale and replaces the purely diffusive time-scale discussed in the spreading wavelet shown in Fig. ?? with a propagating wavefront
265 solution that self-supports its shape. This is illustrated here only for an infinite autocatalytic source term in the reaction-diffusion system (Fig. ??). For a finite autocatalytic reaction the reactive source term has a growth function which is sigmoid, also called a logistic function. This means that the reactant initially grows exponentially, similar to the infinite source, followed by linear reactant growth and a final zero-growth branch. These general solutions imply different shapes of the self-supporting propagating wave and, depending on the value of the diffusivities, also a finite life-time of the wave. waves may wish to
270 continue straight into the following application of the equation to characteristic earthquakes.

This geologically more relevant situation is described in Molotkov and Vakulenko (1993). The authors describe generalised reaction-diffusion systems and find that the wave behaviour depends on only three parameters. For small wavefront curvature the autowave is described by the two parameters of the infinite source term solution discussed above, while for the more general case the normal velocity of the front may contain the front curvature as an additional parameter. The additional dependence
275 of the wave function on the curvature of the concentration field arises because of the fact that $\frac{\partial C_i}{\partial t}$ is proportional to the curvature of the wavefront. For regions of the wavefront where the curvature is negative the concentration must decrease at a rate proportional to the magnitude of the curvature. Conversely, the concentration must increase where the wavefront curvature is positive.

Summarizing the above findings, we can now characterise the reaction-diffusion thermodynamic system by five key features:
280 i.) a bistable or multistable (for several reactions) region with a stable stationary mode and a mode for the nucleation of propagating autowaves above a critical activation threshold; ii) in the activated state, the wavefront separates two regions, a local region characterised by the particular THMC diffusional length scale L_d affected by the reactions R_i , and a large region at $> L_d$ which is outside the reaction-diffusion wave; iii) for long time scales, the wavefield is governed by characteristic self-oscillatory motions which for bistable systems are described by just three parameters. For multistable systems chaotic
285 oscillations are expected (Molotkov and Vakulenko, 1993). For the analysis of this complicated system we will propose to use perturbation theory and illustrate the approach through some basic concepts of signal processing. In the bistable system the Fisher-Kolmogorov wave is a self-propagation dissipative wave at a characteristic wave speed whose lower limit can be quantified by the square root of the Damköhler number times the diffusivity normalised by the characteristic diffusion length scale L_d ; (iv) the propagating wave exponentially scatters information about its initial condition, and the wavefield only carries
290 information about the dissipative properties into the far-field; this is an important differentiation to waves in the conservative system (e.g. elastic waves) where the wave at a long-distance still carries information about its initial conditions; (v) the wave speed thus becomes a fundamental material constant defined by the rates of the dissipative THMC processes as:

$$v_i = 4 \frac{\zeta}{L_d} \sqrt{\text{Da}_i}.$$

295 As the spreading wavefronts are self-supporting and can propagate upwards in scale, we propose that this material velocity not only applies to the above discussed chemical reaction-diffusion equations but to all reaction-diffusion equations of the THMC-coupled system. In this proposition, the propagating multiscale and multiphysics waves provide the capacity to link the different THMC-length-scales and could explain the multifractal nature of earthquakes. The approach allows a significant simplification of the earthquake physics problem as the exponential rate of approaching the Kolmogorov limit of a self-oscillating wavefront shown in Fig. ?? can be simplified by replacing the nonlinear source term through a set of at least two linear coupled partial differential THMC diffusion equations which will be discussed in the next section. At a given scale, the Kolmogorov wave velocity limit allows a characterisation of the important physics in terms of the wave velocity. With the autowave approach, one can turn any non-linear perturbation of the local source into a linear propagating waveform only governed by the dissipative material properties. Autowaves will by themselves recover a characteristic wavefield dictated by the reaction-diffusion rate constants.

305 This characteristic behaviour is used, for instance, in medicine where autowaves are encountered in many fields. The electrical nerve impulses that drive a regular heart beat are an example (Antonioletti et al., 2017). The authors describe how the characteristic recovery of the autowave waveform after a random perturbation can be used, for instance, for defibrillation strategies (a small electrical stimulus applied through a pacemaker) for treatment of life-threatening heart arrhythmia. In this sense, earthquake physics might profit from an understanding of the partial differential equations developed in mathematical biology, epidemiology (wave-like propagation of viruses) and other biomedical applications for which numerical open-source tools are available. One such tool is the "heart beat box" (Antonioletti et al., 2017) which uses a mathematical formulation of the human heart in terms of a coupled electro-mechanical reaction-diffusion equations similar to the coupled reaction-diffusion equations discussed above.

315 The foregoing results The results summarised in the appendix were based on the generalisation of a first-order autocatalytic reaction. Very few practical examples will be first order, and we need to consider the generalised case of a reaction that depends on the concentrations of a second-order reactant-reaction of one component or any number of additional reactions and their equivalent THMC processes. ~~To extend the discussion to~~ When considering more than one reaction, ~~we apply the Fisher reaction term to more than one interdependent reactant. That means in chemical terms that the~~ the concentration of second- or higher-order reactions depends on the concentration of a second- or higher number of species. This will add additional dynam- ics to the system response. ~~To isolate the effect of this additional feedback it is useful to neglect the spatial response and neglect diffusion. Mathematically, such an interdependent coupling of reaction rates is expressed by just considering the reaction term for two cross-linked autocatalytic equations. This is known as the Lotka-Volterra predator-prey model (Lotka, 1920), which beautifully illustrates the generic behaviour of a coupled system in time. The interaction with the spatial response~~ In the case of two reactions the system can display a perfectly regular oscillator. A situation where two reaction-self-diffusion equations

325 are coupled will be discussed later. next. In the example discussed the two reaction terms are a pressure source term from a chemical dissolution reaction and a temperature source term from shear heating.

2.1 Periodicity in time: Lotka-Volterra Waves

The Lotka-Volterra predator-prey model couples two autocatalytic reactions-

$A + X \rightarrow 2X$ prey (X) have an infinite supply of food (A) and multiply

$Y + X \rightarrow 2Y$ predators (Y) eat prey (X) and multiply as a consequence.

330 Coupling between the two autocatalytic reactions occurs because the predators can only multiply if they eat prey. Similar to the above assumption for the derivation of the limiting wave speed, we assume that the food supply A for the prey is infinite and without predators there would be an exponential growth of prey. In chemical terms for the molar concentrations, this leads to the following rate equations (Lotka, 1920):-

$$\frac{d[X]}{dt} = k_1[A][X] - k_2[X][Y]$$

$$\frac{d[Y]}{dt} = k_2[X][Y] - k_3[Y],$$

335 where k_1 and k_2 are reaction rates of the autocatalytic reactions derived from empirical/phenomenological postulates. To close the system a third rate k_3 must be introduced that quantifies the rate of death of predators as the death rate of prey is already included in the reproduction equation for the predator. We can evaluate the equilibrium points of the system by setting $\frac{d[X]}{dt} = \frac{d[Y]}{dt} = 0$ and obtain following condition for the rates:-

$$X = \frac{k_1}{k_2} [A]$$

$$Y = \frac{k_2}{k_3}.$$

340 Another equilibrium point is where the predators consume all prey leading to the extinction of both species. Integrating the Lotka-Volterra *ode* numerically reveals the fundamental oscillatory behaviour of coupled reactive systems shown in Fig. ??-. The Lotka-Volterra oscillator represents the fundamental behaviour of coupled reactive systems. (a) The phase plot with the two equilibrium points (green and orange dots). (b) The corresponding time-evolution of one of the cycles in the phase plot. Predators are in red and prey in blue. The figure shows a simple calculation of the Lotka-Volterra oscillator model in
345 Mathematica (2020). Lotka-Volterra Tutorials are also available allowing for incorporation of a fourth rate constant for the level of predation (Mathematica, 2020).)

The Lotka-Volterra oscillator applies to second-order and higher-order reactions where multiple oscillators may be encountered. We posit here that the fundamental analysis can be transferred from the classical biological system (predator-prey, infectious diseases, etc.) and chemical reactions to all coupled reactive source terms of the THMC reaction-diffusion system. When
350 looking for a possible Lotka-Volterra oscillator in earthquake dynamics, one would start with trying to identify first a perfectly regular oscillator which would involve only two coupled THMC equations. To then generalise the approach one would continue to the generalised Lotka-Volterra oscillator, such as the three-species oscillators, which explain the transition to chaos. An example is shown in Fig. 12.4 in Flake (1998).-

2.0.1 Lotka-Volterra type earthquake sequences

355 ~~There are examples of characteristic~~

2.1 Application of two reaction-self-diffusion equations to characteristic earthquakes

Characteristic earthquakes with some typical regularity in their recurrence, e.g. the Parkfield example (Wiemer and Wyss, 1997) have been a matter of special interest in seismology. Prominent example of earthquakes with characteristic recurrence periods are the Parkfield earthquake sequence (Wiemer and Wyss, 1997), and also the Episodic Tremor and Slip (ETS) events recorded
360 in Japan, Cascadia and Hikurangi subduction system (Gomberg, 2010). These have been interpreted with Such events are typically modelled by spring-slider models based on empirical friction data (Ohtani et al., 2019). However, attempts have also been made to explain the friction evolution by the dehydration reaction of serpentinite explaining the phenomenon of ETS events by coupling two reaction-self-diffusion equations resulting in a perfectly periodic thermo-chemical TC oscillator model (Poulet et al., 2014b) shown in Fig. 3. It was shown that a-

365 The approach relies on the tight coupling of the temperature reaction-diffusion equation with the pressure reaction-diffusion equation (Alevizos et al., 2014; Veveakis et al., 2014) can lead to the reaction-self-diffusion equation with a chemical reaction-self-diffusion equation (Alevizos et al., 2014; Veveakis et al., 2014) which can lead for a highly nonlinear source term to excitation waves with a characteristic perfectly periodic Lotka-Volterra-type oscillatory response in the temperature-pressure plot (Fig. 3). The authors also show an example where, by considering an additional oscillator, a transition to chaos can be modelled (Poulet
370 et al., 2014b). The basic element of the model is a chemical decomposition function of the type $AB \rightleftharpoons A + B$. This dissolution decomposition reaction is different to the autocatalytic reaction described above. The equivalent autocatalytic element in this decomposition reaction is discussed in the appendix. The nonlinear element which is necessary to trigger excitation waves is not stemming from the linear chemical dehydration reaction but introduced through shear heating feedback during fault slip, triggering power-law creep. Shear heating in turn drives the thermally induced dissolution. Poulet et al. (2014b) numerically
375 investigated the potential candidate source mechanism of a thermally induced dissolution reaction of serpentinite in the fault zone originally proposed by Obara (2002). In that model solid serpentinite (phase AB) decomposes into a solid phase A (Antigorite) and a fluid phase B (water) upon application of a heat source from shear heating.

2.2 Periodicity in space: Cross-diffusion Waves

It is encouraging that a simple chemical reaction model of the normally fine-grained serpentine crystal at say millimetre scale
380 can be used to model an ETS instability at plate scale, say around 100-1000 km scale. Communication of information over eight to nine orders of magnitude may hence be possible under special circumstances. This leads to the proposition that progress can be made by investigating the multiscale physics of the THMC reaction-diffusion system in the Earth in further detail. In addition to the timing and displacement information obtained from GPS and seismic stations, the spatial information related to the diffusion term could be investigated to verify the model. A key observable would be the propagating wavefront that would
385 be expected from the above discussion on reaction-diffusion time scales ~~as illustrated in the appendix (Fig. ??).~~




Figure 3. The characteristic period of the Cascadia ETS sequence interpreted with a reaction-diffusion oscillator model (Poulet et al., 2014b). (a) The phase diagram between *A* and *B* corresponds to the slow creep of the serpentinite slowly raising the temperature to the critical level for the onset of the dehydration reaction. The segment between *B* and *C* corresponds to the dehydration reaction that coincides with the tremor and slips event. The following segment between *C* and *A* is the diffusion-dominated field. (b) shows the corresponding normalised strain rate with the sharp peak corresponding to the tremor event.

In the case of the serpentinite decomposition reaction, the diffusive wavefront would propagate normal to the main fault plane as the chemical decomposition reaction involves significant volume reduction which would lead to a contraction of the central fault plane and a characteristic width of the fault plane. This process zone is not exposed in active subduction systems but can be found in geological exposures of fossil faults. An excellent example is the Glarus Thrust which has been modelled
 390 by the ~~Lotka-Volterra-type~~ same perfectly periodic two reaction-self-diffusion equation oscillator approach using a carbonate decomposition reaction (Poulet et al., 2014a). The model includes ~~diffusion-self-diffusion~~ and therefore the expected spatial response can be tested as well. The model is shown to be capable to reproduce the process zone around the central fault plane which is documented in many fault zones (Chester et al., 2013). Another textbook example is the ~~Punchball~~ Punchbowl Fault in California where a series of deformation mechanisms were described (Schulz and Evans, 2000).

395 ~~Synchronous or staggered deformation mechanisms are a general observation (Vermilye and Scholz, 1998) and require expansion of the chemical decomposition reaction model to include other important meso- to macroscopic deformation mechanisms. Additionally, microstructure, geometric complexity, and multiple deformation mechanisms lead to a stochastic element at the meso-scale whose role in the transfer of the information from micro- to large-scale in real geological applications is not yet discussed. In the following we will discuss whether these meso-scale stochastic processes lead to a loss or an enhanced coupling from small to large scale. x~~
 400

2.2 Consideration of cross-diffusion

Before introducing the concept of cross-diffusion, we might consider what is lacking for investigating the earthquake source mechanism by the reaction-self-diffusion equation without the cross-diffusion term. If indeed the reaction-self-diffusion equation were sufficient to describe the earthquake source mechanism the approach would allow a significant simplification through the

405 coarse-graining approach. The exponential rate of approaching the self-oscillating wavefront of the Fisher-Kolmogorov–Petrovsky–Piskunov (FKPP) wave discussed in the appendix (Fig. ??) could be used as a simplification and any nonlocal effects be ignored. The above example of the reaction-self-diffusion equation for ETS sequences explains the earthquake source mechanism by a similar mechanism as the one proposed for landslides (Vardoulakis, 2001). If indeed the fluid release due chemical dissolution were a universal mechanism that leads directly to earthquakes, coarse-graining approaches may be able to use the FKPP wave
410 velocity limit to allow a characterisation of the important physics of the dehydration mechanism. At coarse-grained level the wave velocity would just be defined through the limit velocity derived in the appendix (Eq. 16) and may be detected from the seismic records of the episodic tremors. This offers a significant simplification as the approach would allow - not only to turn non-linear effect of a local reactive source term (thermal pressurisation) into a propagating waveform that propagates at constant speed - but also make sure that the wave velocity is governed by the dissipative material properties irrespective of the
415 initial conditions. Excitation waves supported by local reactions will by themselves recover a characteristic wavefield dictated by the reaction-diffusion rate constants.

The reaction-self-diffusion model for the ETS sequences effectively singles out a chemical dissolution process which, as emphasised above, is proposed to operate over all scales. The multifractal nature of earthquakes discussed earlier shows that this is not the general case. What is therefore missing is a means to couple the propagating multiscale and multiphysics waves of
420 different THMC processes. The problem can be addressed by a statistical mechanics approach to the coarse-graining problem. In Fig. 2 we proposed that the missing element for considering mesoscopic complexity in a physics-based earthquake model is a meso-scale approach that captures the link between the vast differences in the diffusional length scale (listed in Table 1 in the appendix) of THMC processes ~~shown in Table 1. In part. In Part 1~~ (Regenauer-Lieb et al., 2021) we proposed that a meso-scale approach can be developed by decomposing the large-scale reaction term R_i into a meso-scale reaction term
425 which requires a meso-scale cross-diffusion term for mass (momentum, energy) balance. This is because the aforementioned cross-scale coupling introduces meso-scale source/sink terms in the individual conservation laws identified by r_T, r_H, r_M and r_C , respectively. The conservation laws must, therefore, be extended to close the equations and allow a multitude of THMC processes to occur simultaneously, which introduces cross-diffusion fluxes.

~~Here we derive the~~ We therefore postulate here that these terms are the critical ingredients that provide the capacity
430 to fire off waves that are controlled by cross-diffusion ~~approach from a different angle by following the coarse-graining operation. Techniques for the quantification of the uncertainty reduction through the coarse-graining operation are the main subject of statistical mechanics (Sethna, 2006). The basic principles can be discussed based on Shannon's entropy, Heisenberg uncertainty relationship, renormalisation theory, and the fluctuation theorem (Evans and Searle, 2002). For a more in-depth discussion and a broader perspective on the different techniques we recommend textbooks providing distillations of 50 years~~
435 ~~of statistical mechanics (Sethna, 2006) and material science applications (Balluffi et al., 2005). Here we present a functional analysis approach of probability theory applied to order parameter fluctuations. The first part of the analysis is often used in signal processing and image analysis (Buades et al., 2005). The following discussion, therefore, explains the convolution filter interpretation of the cross-diffusion waves discussed in part 1 (Regenauer-Lieb et al., 2021). Consider a thermodynamic system as a planar surface from a macroscopic view. At the mesoscopic view, it is made up of subvolumes or more accurately subplanes~~

440 in the current mathematical formulation. A mesoscopic subvolume is highlighted where two propagating diffusion wavelets interact. The discrete system represents the microscopic view where red and blue dots represent individual discrete chemical molecules or predators and prey or indeed generalised thermodynamic ‘micro-engines’ in an activated oscillatory quasi-steady state. We are interested in the assessment of the effect of the mesoscopic collision of micro-engines on the macroscopic system. From an equilibrium statistical mechanics perspective, we are therefore not interested in the local dynamics of
 445 molecules/micro-engines but use a convolution operation to describe the mesoscopic effect. This approach allows investigation of the meso-scale dynamics which feeds into the macro-scale continuum mechanics approach where sufficient time has elapsed so that the flux Q becomes constant and the system has reached its maximum entropy production state (Collins and Houlsby, 1997). The system can then be described by the theory of thermomechanics, ie. the theory of thermodynamics with internal variables (Maugin and Muschik, 1999; Jacquey and Regenauer-Lieb, 2020). This approach also yields the familiar dissipative material
 450 properties/transport coefficients of the classical continuum approach. For constant thermodynamic force flux pairs we obtain for instance: the thermal conductivity of the material, for constant temperature/heat flux (T), permeability for a constant pressure/fluid flow pair (H), viscosity for a constant velocity/momentum flux pair (M), and the chemical diffusivity for a constant chemical potential/diffusion flow (C) pair (Oettinger, 2005).

2.2.1 Gaussian Wavelet convolution as a blurring filter

455 In terms of uncertainty quantification the diffusion wavelet in Eq. 2 and shown in Fig. ?? is identified as a univariate Gaussian probability density function, also called a Gaussian kernel in image processing (Buades et al., 2005). Due to the linear nature of the partial differential equation we note that at different THMC-length-scales and thus explain the observed multifractal nature of earthquakes.

The synchronizing effect of cross-diffusion is well studied for the simple FitzHugh-Nagumo relaxation electrical oscillator
 460 where the following analysis is valid for any number of interactions. Fig. ?? shows an example of interaction of two diffusion wavelets with the probability distribution functions having an opposite sign of velocities implying a collision of the two wavelets due to their opposing direction of travel (Eq. 16).

$$f(x) = \frac{1}{L_d(f)\sqrt{\pi}} \exp\left(-\frac{(x-\mu_f)^2}{L_d(f)^2}\right)$$

$$g(x) = \frac{1}{L_d(g)\sqrt{\pi}} \exp\left(-\frac{(x-\mu_g)^2}{2L_d(g)^2}\right),$$

where μ_f and μ_g are the function centroids of the the function $f(x)$ and $g(x)$ known as the mean in probability theory. Since
 465 both wavelets are moving towards each other we would like to use a Lagrangian reference frame, here arbitrarily chosen to be $f(x-\tau)$, to assess how the shape of this function is modified by the passage of the function $g(\tau)$. The convolution operation is commutative, and we can also use the opposite reference frame. The convolution operation is defined by:-

$$\int_{-\infty}^{\infty} f(x-\tau)g(\tau)d\tau = f \star g,$$

where τ denotes a translation in the positive x -direction. Due to the translational symmetry of the diffusion wavelet, it is convenient to use the Fourier transform F as the eigenfunctions of the translation τ operation are complex plane waves.

$$F(f(x)) = \exp(-\pi i k \mu_f) \exp(-\pi^2 L_{d(f)}^2 k^2),$$

where k is the wave-vector of the Fourier transform. The wave-number and wave-vector are defined as $k = |\mathbf{k}| = 2\pi/\lambda$. The convolution operation of function $f(x)$ and $g(x)$ in Fourier space is the product of the Fourier transforms $F(f(x))F(g(x))$. Applying the same Fourier transform as in Eq. ?? to $F(g(x))$ and performing the product with $F(f(x))$ we obtain:

$$F(f(x))F(g(x)) = \exp(-\pi i k (\mu_f + \mu_g)) \exp(-\pi^2 (L_{d(f)} + L_{d(g)})^2 k^2).$$

The first exponential term is the mean amplitude of each Fourier wave-vector which can be decomposed as a real sinus-wave and imaginary cosinus-wave that contains the phase information. The second term is a Gaussian probability density function of the wave-vector.

This result is very useful as it can be used to analyse the behaviour upon the collision of two diffusion wavelets. The first conclusion is that the convolution results in another Gaussian wavelet as can be seen from the comparison of Eqns. ?? and ?. The second conclusion is that the convolved amplitude is reduced by the sum of the function centroids $\mu_f + \mu_g$ in the positive x -direction and the breadth of the wavelet is enlarged by the variance $(L_{d(f)} + L_{d(g)})^2$ of the probability distribution function. The result that the convolution operation reproduces a similar function to the original function is called self-similarity. The Gaussian function is self-similar and defines a linear Gaussian scale-space where space-time relationships can be normalised by the diffusion length. This is an important aspect of coupling across the scale. Another aspect of the Gaussian wavelet is that the 1-D approach presented here can be extended and superposed to any dimension as the function is separable, i.e. it can be applied to any dimension independently. In principle the technique can be extended to anisotropic diffusion, where the introduction of a non-linear space varying Gaussian filter may lead to additional problems discussed next (Kichenassamy, 1997).

2.2.1 Gaussian Wavelet convolution as a sharpening filter

So far we have discussed the situation where the meso-scale convolution of the two diffusion wavelets appears as a smoothing filter of colliding Gaussian wavelets, where high frequencies are quickly reduced and the high-frequency wavelet gets preferentially diffused. This class of Gaussian low pass filter problems is not of interest for the nucleation of earthquakes as the small scale local instabilities triggered by chemical reactions are filtered out. The opposite situation of a sharpening filter is, however, very interesting. A sharpening filter is an expression used in image processing when applying a deconvolution operation using a Dirac delta convolution kernel minus a Gaussian blur kernel. This is effectively an anti-diffusion filter, also known as an uphill diffusion operation, which may lead to problems as it may violate thermodynamics without applying further restrictions (Ulmer, 2010). This problem is well known in image processing for modelling anisotropic diffusion where it is known as the Perona-Malik paradox (Kichenassamy, 1997).

500 However, the sharpening filter problem can be made thermodynamically consistent. The method has been described in part 1 (Regenauer-Lieb et al., 2021) through the consideration of meso-scale processes and the physics of acceleration waves that radiate energy into the environment and regularise the local inconsistencies through their interaction with a stabilising constant large-scale thermodynamic flux. The communication mechanism between the meso-scale and macro-scale is a travelling acceleration wave. We have shown through mass and momentum balance that a local reaction term requests a local self-diffusion
 505 terms are replaced by linear cross-diffusion term. The approach in part 1 (Regenauer-Lieb et al., 2021) was based on a physics and mechanics of solids approach which essentially looks at the meso-scale negative diffusion process from a macroscale continuum mechanics perspective characterised by a positive diffusivity. Can we come to the same conclusion by looking at the meso-scale from a chemical-scale perspective by considering the mobility of atoms underpinning the meso-scale process in the light of the global changes of the free energy?

510 The observation of spontaneous unmixing from a fully diffused, intermingled, and unstable thermodynamic phase of two different phases, e.g. solid and fluid (spinodal decomposition), is mathematically equivalent to an uphill diffusion problem. When interpreting the phenomenon through a linearised Fickian diffusion Ansatz (Eq. 2) we come to the perplexing conclusion that Eq. 2 has a thermodynamically inconsistent negative diffusivity (uphill diffusion). Note that the driving force for spinodal decomposition is not a chemical reaction but a reduction in the bulk free energy of the homogeneous mixture, which is
 515 thermodynamically unstable. The breakthrough in understanding this process in terms of a thermodynamically consistent approach to the apparent uphill diffusion phenomenon of spinodal decomposition is attributed to ? and coworkers.

A detailed description of the approach is given in Balluffi et al. (2005). The solution is to consider a meso-scale length scale at the spinodal reaction front (hereafter called the spinodal) and express the diffusion process as a product of the diffusive mobility of atoms M , which must be a positive term to satisfy the second law and a gradient term of the large-scale generalised
 520 chemical potential. The gradient in the generalised chemical potential, in turn, is made up of a product of a meso-scale negative second-order derivative of the free energy f of the mixture concerning the concentration C and a positive gradient of the concentration. This situation leads to a non-linear interdiffusivity $\tilde{D} = M \frac{\partial^2 f}{\partial C^2}$ which is negative at the spinodal.

$$\frac{\partial C}{\partial t} = \tilde{D} \nabla^2 \frac{\partial C}{\partial x}.$$

525 There are two ways to approach this thermodynamic problem which can be solved by considering the meso-scale thermodynamic couplings. The first approach is similar to the one presented in part 1 (Regenauer-Lieb et al., 2021) but developed from a chemical perspective. For this, we decompose the nonlinear interdiffusion coefficient \tilde{D} into n -coupled interdiffusion coefficients \tilde{D}_{ij} expressed as a product of two matrices L_{ik} and Υ_{kj} (Balluffi et al., 2005),

$$\tilde{D}_{ij} = \sum_{k=1}^{N-1} L_{ik} \Upsilon_{kj}.$$

530 where L_{ik} are the classical macro-scale chemical diffusivities, also known as the 'Onsager coefficients', and Υ_{kj} are the meso-scale thermodynamic factors that couple local chemical potentials to concentrations. For the specific case where the local,

meso-scale coupling coefficients are of mechanical origin, due to the effect of the volumetric strain triggered by a concentration change for instance, Υ_{kj} are known as the 'Vegard coefficients' (Balluffi et al., 2005).

For the least complicated multicomponent system the coupled interdiffusion matrix is

$$\tilde{D}_{ij} = \begin{bmatrix} \tilde{D}_{11} & \tilde{D}_{12} \\ \tilde{D}_{21} & \tilde{D}_{22} \end{bmatrix}.$$

535 We will use the compact notation for the extended general multicomponent case and introduce the stability criterion for the interdiffusion matrix later. For the spinodal decomposition case an instability is triggered when the meso-scale couplings have a negative interdiffusivity \tilde{D}_{ij} and a local spinodal wavefront develops. A negative interdiffusivity leads to an exponential growth of any perturbation exactly like in the previously discussed reaction-diffusion case.

540 For discussing the criterion for instability we follow the solution strategy originally suggested by ?. For this we stay in the Fourier space and consider the general linearised diffusion problem:

$$\underline{C_i(x) - C_m = \int A(k) \exp(ikx) dk},$$

whereby C_m is the average composition used to linearise \tilde{D} into the components of the two phases. $A(k)$ are the amplitudes of each Fourier mode k being

$$\underline{A(k) = \frac{1}{2\pi} \int (C_i - C_m) \exp(-ikx) dx}.$$

545 Inserting the chosen interdiffusion couplings into the generalised solution Ansatz we can estimate the response of the system through a perturbation analysis of the wave vector in Fourier space whereby

$$\underline{\frac{\partial A(k, x)}{\partial t} = R(k) A(k)},$$

and $R(k)$ is the amplification factor. This generic perturbation analysis has the following solution:

$$\underline{A(k, t) = A(k, 0) \exp(R(k)t)}.$$

550 This analysis divides the spinodal decomposition model into two areas. For the local scale around the spinodal composition wave we expect positive values of $R(k)$ and the convolution of the two inter-diffusing phases is unstable and results in exponential growth of composition waves defined in Eq. ??, i.e. a sharpening filter with the maximum wave vector $\frac{\partial R(k)}{\partial k} = 0$. Away from the spinodal composition waves, the amplification factor is smaller than zero ($R(k) < 0$), and the system is stable. Figure ?? shows three time steps in the temporal evolution of a simple Cahn-Hilliard system illustrating dominant wavelength growth at the maximum amplification factor $R(k)$.

Cahn-Hilliard phase-field simulation of the spinodal decomposition controlled by the lowest wavenumber k_{min} (longest wavelength) on the maximum amplification factor $R(k)$. The time and space dependent species concentration profile C_i/C_0

is plotted as a function of the normalised domain x . The characteristic long wavelength pattern of the spinodal decomposition wave develops at time step three. Numerical simulations for the Cahn-Hilliard system are performed using a phase-field simulator described in Clavijo et al. (2019).

To visualize the spinodal wavelength changes in the system, we plot the normalized species concentration in the x direction. The dynamics increases the spinodal wavelength as terms (Biktashev and Tsyganov, 2016). The electrical nerve impulses that drive a regular heart beat are an example. Antonioletti et al. (2017) describe how the characteristic recovery of the system goes to the steady-state which drives the phase-separation process. For Fig. ?? we solve the Cahn-Hilliard equation using PetIGA in a 2D configuration with 64 finite elements in each direction. PetIGA is an reaction-cross-diffusion excitation waveform after a random perturbation can be used, for instance, for defibrillation strategies (a small electrical stimulus applied through a pacemaker) for treatment of life-threatening heart arrhythmia. In this sense, earthquake physics might profit from an understanding of the partial differential equations developed in mathematical biology, epidemiology (wave-like propagation of viruses) and other biomedical applications for which numerical open-source framework for high-performance computing that solves efficiently phase-field equations (Dalcin et al., 2016). The material parameters for the Cahn-Hilliard system allow for phase separation together with spinodal decomposition. Moreover, we use the isometrical analysis method to successfully discretize and solve the equation in its primal form. Such a method allows for high-order, highly-continuous basis functions (Cottrell et al., 2009). tools are available. One such tool is the "heart beat box" (Antonioletti et al., 2017) which uses a mathematical formulation of the human heart in terms of a FitzHugh-Nagumo cross-diffusion formulation.

For the Similar cross coupling terms are also used in other fields of physics where the explicit cross-diffusion formulation response of the system to wave perturbations is tested by a complex-valued wave function. The complex valued function embeds cross-diffusion as it expresses the bi-directional response of each diffusively coupled system through a mutually cross-coupled diffusion problem. The generalisation to a multi-component system with N -coupled components, we evaluate the bi-directional response of each coupled system through a complex-valued wave function perturbation. This (note no summation convention assumed here) is also known as an order parameter perturbation analysis fluctuation analysis. The analysis uses the response functions of Fourier component variational perturbations (Balluffi et al., 2005) in the sense that:

$$i \frac{\partial \psi(k, t)}{\partial t} = -R(k) \tilde{D}_{ij} \nabla^2 A(k, t), \quad (3)$$

where $i\psi(k, t)$ denotes the complex position-space wave function and $A(k, t)$ are the amplitudes associated with each Fourier mode. The amplification factor $R(k)$ depends on the Fourier mode k and the direction of the amplification controlled by the diffusivities \tilde{D}_{ij} . Assuming $i\psi(k, t) = u(k, t) + iv(k, t)$, we recover the cross-diffusion type relationship of Eq. 24 in part Part 1 (Regenauer-Lieb et al., 2021) where the probability amplitude of the u -wave depends on the cross-diffusional coupling to the

v -wave. Vice versa, the probability amplitude of the v -wave depends on the cross-diffusion of u :

$$\frac{\partial u(k, t)}{\partial t} = -\tilde{D}_{ij} \nabla^2 v(k, t) \quad (4a)$$

590 $\frac{\partial v(k, t)}{\partial t} = \tilde{D}_{ji} \nabla^2 u(k, t). \quad (4b)$

This bi-directional relationship between u - and v - wave, ~~more generally known as the Kramers-Kronig relationship~~ has provided a robust approach to investigate kinetics of order parameters, phase transitions, and fluctuations (Balluffi et al., 2005; Sethna, 2006) (Sethna, 2006). We will use this transformation later to show how our cross-diffusion formulation converts into the non-linear Schrödinger equation for a specific set of parameters. We will also show how an explicit consideration of the cross-diffusion terms can trigger a new class of waves which has not yet been described for the earth system.

~~An important conclusion from this formulation is gained by a comparison of the partial differential Equations 4 and ??.~~ ~~The~~ In what follows we first add the important reaction term to this approach to provide a link to the generalised approach in Part 1 (Regenauer-Lieb et al., 2021), then present laboratory examples of diffusion waves, followed by an extension of the hydromechanical (HM) coupled cross-diffusion ~~problem leads at a quasi-steady state to a periodicity in space in the same way as the Lotka-Volterra oscillator model leads to a periodicity in time at quasi-steady state.~~ The partial differential equations for cross-couplings are the same except that the cross-coupling coefficients in the Lotka-Volterra oscillator (Eq. ??) are reaction rates and the cross-coupling coefficients in the cross-diffusion formulation (Eq. 4) are diffusivities. model (Hu et al., 2020) into a specific nonlocal formulation that may be relevant for studying the physics of earthquakes (Crampin and Gao, 2015) and conclude with a presentation on how this set of equations may lead to or trigger a catastrophic instability.

605 2.3 Cross-diffusion and its role in coupling of instabilities across scales

~~After discussion of the isolated spatial (cross-diffusion) and temporal (autocatalytic reaction) oscillators we~~ We can now extend the ~~above approach~~ reaction self-diffusion equation for full space-time coupling for multiple reaction-diffusion equations and re-introduce reactions. An exemplary convolution of the mesoscopic oscillators is the self-similar Gaussian wavelet in space and time, which is also the Green's function of the local equilibrium statistical mechanics approach. In the linear case, any number of wavelets can be superposed, and a Fourier transform is an ideal procedure to capture the effect of multiple oscillators and local heterogeneities on the macro-system. In part Part 1 (Regenauer-Lieb et al., 2021) we proposed to generalise the cross-diffusion approach, which is well known in chemistry (Manning, 1970), to more general THMC terms defining cross-diffusion as the phenomenon where a gradient of one generalised thermodynamic force of species C_j drives another generalised thermodynamic flux of species C_i , described by

615 $\frac{DC_i}{Dt} = \tilde{D}_{ii} \nabla^2 C_i + \sum_{j \neq i} \tilde{D}_{ij} \nabla^2 C_j + r_i \quad . \quad (5)$

The species j is identified as the cross-diffusion species other than the species i . Introducing a fully populated ($N \times N$) diffusion matrix \tilde{D}_{ij} , equation (5) can [\(using explicit summation instead of Einstein convention\)](#) also be written as

$$\frac{DC_i}{Dt} = \sum_{k=1}^N \tilde{D}_{ij} \nabla^2 C_k + r_i \quad , \quad (6)$$

whereby the classical (self-)diffusive length scale of each THMC process is defined by $\sqrt{4\tilde{D}_{ii}t}$. The cross-diffusion approach
 620 introduces also a new meso-scale coupling length scale that can provide a link between the large scale self-diffusion length
 scales of the THMC processes. In [part Part 1](#) (Regenauer-Lieb et al., 2021) we have shown that the cross-diffusion length scale
 $\sqrt{4\tilde{D}_{ij}t}$ is defined by the kinetic material properties which can be evaluated by measuring the velocity of cross-diffusion
 waves in analogy to the generalisation of Eq. ?? for the [Fisher-Kolmogorov-FKPP](#) wave. This leads to the equation for the
 wavespeed in Eq. 16 defined by the generalised Damköhler number and the cross-diffusion length scale $\sqrt{4\tilde{D}_{ij}t}$. Using the
 625 alternative mechanical formulation the cross-diffusional wave speed turns out to be (Coleman and Gurtin, 1965)

$$v_{cross} = \sqrt{\frac{C}{\rho}} \quad . \quad (7)$$

where ρ is the [instantaneous](#) density and C is the [4th-order eigenvalue of the](#) material stiffness tensor also known as the
 acoustic tensor discussed in [part Part 1](#) (Regenauer-Lieb et al., 2021). The stability criterion of the diffusion problem is fully
 characterized by the diffusion matrix \tilde{D}_{ij} with the diagonal elements \tilde{D}_{ii} describing the normal self-diffusion and the
 630 off-diagonal elements the cross-diffusion processes enabling coupling across scales. For consistency with the second law, all
 eigenvalues of the diffusion matrix must be real and positive, and hence the determinant of the diffusion matrix $\text{Det}(\tilde{D}_{ij}) > 0$
[Det\(\$\tilde{D}_{ij}\$ \) > 0](#) as well as the trace of the diffusion matrix must be larger than zero. Complex eigenvalues of \tilde{D}_{ij} result in
 oscillatory relaxation of any small perturbation to the equilibrium state, even in the absence of reaction (Vanag and Epstein,
 2009).

635 [Any For a given sufficiently nonlinear reactive source term that supports nucleation of excitation waves any](#) local thermo-
 dynamic incompatibility that leads to complex eigenvalues of \tilde{D}_{ij} [must radiate](#) \tilde{D}_{ij} [radiates](#) energy in oscillatory instabilities
 by so-called acceleration waves (Regenauer-Lieb et al., 2021), relaxing to the equilibrium state (Vanag and Epstein, 2009) to
 recover the second law of thermodynamics at large scale. This statement is at the heart of the nucleation of the cross-diffusional
 wave phenomenon. We will show in the following sections that the above described cross-diffusion formulation (Vanag and
 640 Epstein, 2009) can be extended to develop a generic multiphysics and multiscale THMC coupling approach to earthquake
 instabilities [occur](#). This formulation implies a coupled cascade of THMC feedbacks over multiple diffusional length scales
 honouring the reciprocal multiscale interplay of thermodynamic forces and fluxes.

By extending the diagonal diffusion matrix through the cross-diffusion coefficients in equation 6, a [new](#)-cross-diffusion wave
 phenomenon is revealed [that incorporates chemical waves at its lowest scale as shown in Part 1](#) (Regenauer-Lieb et al., 2021).
 645 For the simple case of hydro-mechanical (HM) coupling, we have recently reported that the upscaled volumetric chemical
 strains can result in a hydromechanically coupled cross-diffusional pressure wave phenomenon (Hu et al., 2020).

The important element of cross-diffusion ~~waves terms~~ for earthquake physics is their capability to link one thermodynamic force with a thermodynamic flux at a different scale, thus synchronising the dynamics over vastly different diffusional time and length scales. This important aspect of earthquake physics was previously overlooked. The approach not only explains
650 the multifractal nature of earthquakes but raises the possibility that dissipative waves can be detected before earthquake instabilities. Before discussing the potential earthquake application, we summarise observations from ~~the laboratory and the field~~laboratory experiments and propose a coupled hydromechanical (HM) reaction-cross-diffusion equation which may be used as a simplification for the fully coupled THMC problem.

3 Laboratory and field observations of diffusion waves

655 ~~So far In Part 1 (Regenauer-Lieb et al., 2021) we have discussed reaction-diffusion waves from an idealised continuum mechanics (Regenauer-Lieb et al., 2021) and a chemistry-based (this paper) viewpoint. We have addressed the uncertainty relationship which is implicit when going from a discrete to a continuum system~~viewpoint and in this paper we have employed a nonlocal coarse-graining approach. However, both viewpoints are based on mathematically ideal worlds. For real laboratory and field applications, the processes are often occluded to direct observations, and the self- and cross-diffusion coefficients cannot be
660 easily derived. ~~The verification or falsification of the reaction-diffusion "wave mechanics" approach is facing the following difficulties: (i.) Field observations offer a frozen-in snapshot of the dynamic process and may enable a direct identification of cross-diffusion length scales through observation of the microstructure. However, the assumption is that the reaction-diffusion wave has been given sufficient time to reach its maximum wavenumber as shown in Step 3 in Fig. ??.~~ (ii.) Laboratory measurements offer insight into the dynamics, but they have the drawback that the microstructural processes at the meso-scale
665 are difficult to monitor directly (Sehrank et al., 2020), and what is recorded is often an average response. This averaging requirement some heuristic assumptions and simplifications. (iii.) ~~The third and perhaps most important abstraction is that in the laboratory or field reference frame we most often see laboratory or earthquake instabilities as mechanical and not as a chemical, fluid, or thermal instability. The third problem can therefore only be addressed by exploring the solution space mathematically. This~~

670 This paper proposes that earthquakes are a THMC convolution of all of ~~these~~ instabilities that cause volumetric and shear strains due to their different micromechanics. In the following, we will address the three problems sequentially using field and laboratory examples before exploring a simple analytical solution applied to earthquake physics.

3.1 Diffusion waves at chemical scale

At first sight, we may expect that field examples offer the most direct access to the verification of the cross-diffusion wave
675 hypothesis, however, this is curtailed by following difficulties. The foregoing discussion on the Lotka-Volterra oscillator model compared to the spinodal composition wave highlights the fact that oscillatory responses can either stem from an autocatalytic reaction (Lotka-Volterra, oscillation in time) or an effective uphill diffusivity (oscillation in space) or both. In a geological field example we can investigate the frozen-in spatial response but cannot verify/falsify the theoretical expectations for the

time evolution and hence, we cannot quantify the composite effect of the different wave speeds. From a mathematical point
680 of view we may expect two end-member cases. The first case is the temporal oscillator case that is governing the system as in
the Lotka-Volterra model (Eq. ??) and the other is the spatial oscillator case that is governing the system in the form of waves
fixed in space. This spatial oscillator is obtained by swapping the rate constants of the Lotka-Volterra cross-coupling rates by
cross-diffusion coefficients as shown in Eq. 4. These two end-member cases are exactly what has been proposed to explain
periodic patterns in the field (L'Heureux, 2013).

685 Accordingly, time-periodic chemical systems have been attributed to a mechanism discovered in reaction-diffusion experiments
with hydrogels where colloidal precipitation patterns with a self-propagating rhythmic growth signature have been recorded
(Liesegang, 1906). This special class of Turing precipitation patterns, encountered in reaction-diffusion systems, have been
attributed to a large class of oscillatory pattern formation observed in chemistry, physics, biology (shells), medicine (gallstone,
cysts, tumours, inflamed tissues) and geology (Nabika et al., 2020). In geology these oscillatory precipitation patterns are
690 encountered in a wide range of geological settings (igneous, sedimentary, hydrothermal and metamorphic) and classified as
"Liesegang" patterns (L'Heureux, 2013). Rhythmic Liesegang patterns come in many guises and for widely different rock
compositions. Figure ?? shows a typical set of Liesegang patterns encountered in a porous sandstone on the East Coast of
Australia. Although the Liesegang patterns form a striking pattern found everywhere in the coastal exposure in the greater
Sydney area little fundamental work has been done on the investigation of these exposures. Comparisons with similar rocks
695 found widespread around the globe have been used to propose a microbially induced oxidation of siderite by iron-oxidizing
bacteria (e.g. *Gallionella* spp.) with following geochemically induced self-organisation of the reduced iron as a possible source
for the pattern (Kettler et al., 2015).

Liesegang patterns in Hawkesbury Sandstone, NSW where several sets of Liesegang patterns are observed. Siderite is a
common constituent in the Hawkesbury Sandstone. After an oxidation reaction characteristic limonite, lepidocrite and goethite
700 precipitation patterns are formed. These oscillatory reaction-diffusion patterns in the porous sandstone are often oblique to
the sedimentary layering and commonly related to fractures which act as preferred fluid pathways. A possible explanation
suggested by Ron Vernon (pers. comm.) is that oxidation reactions of siderite ($FeCO_3$) with percolating oxidized water
through joints ($2FeCO_3 + H_2O + O \rightarrow 2FeO(OH) + 2CO_2$) have built the circular patterns shown in a) while a reduction
reaction of percolating acid solutions ($2FeO(OH) + 2H^+ \rightarrow 2Fe^{2+} + 2H_2O + O_2$) may explain the bleaching around the
705 joint in b). Photographs from Killcare, courtesy of Ron Vernon.

Although Liesegang patterns have been encountered in many guises and more than 100 years of research on the subject has
supplied a wealth of observations, a recent review (Nabika et al., 2020) reveals that the basic mechanism is still controversially
discussed. Accordingly, the basic mechanism is attributed to two competing models classified by Nabika et al. (2020) as
pre-nucleation and post-nucleation models. The pre-nucleation model describes a time-transient propagating dissolution-precipitation
710 wave (L'Heureux, 2013) where the precipitate and depleted zones are frozen in at the nucleation and growth step. In contrast the
post-nucleation model follows as a quasi-static pattern which emerges as a long time scale pattern after the reaction-diffusion
front has propagated through the medium. The latter model has been used to explain the origin and mechanism for banded
iron formations (Wang et al., 2009) and striped zoning in agate (Wang and Merino, 1995). A more recent study of mineralising

715 systems interpreted as long-time scale solution of the Gray-Scott reaction-diffusion system is found in Oberst et al. (2018).
The Gray-Scott model neglects the meso-scale cross-diffusion term but considers self-replicating patterns of the mineral
system reproduced by inclusion of a non-linear source term. This approach therefore jumps straight to the long-time scale
solution as for the equivalent mechanical case of the Korteweg-deVries – or the non-linear Schrödinger equations discussed
further below.

720 A universal mechanism for Liesegang patterns probably encompasses both end-members in a mixture (Nabika et al., 2020).
This conclusion is supported by similarity of the Liesegang patterns to the spinodal decomposition models. In these models the
mathematical analysis of the Cahn-Hilliard spinodal composition wave reveals a surprisingly rich field of linear and non-linear
wavefronts with possible cross-overs from temporal to spatial wavenumber selection and wave speeds (Scheel, 2017). Such a
complex behaviour may be expected from the above discussion that includes the partial differential equation of a Lotka-Volterra
725 oscillator in time combined with the cross-diffusion oscillator in space. Due to the complexity of the behaviour we therefore
recommend to use the perturbation theory in terms of a Kramers-Kronig formalism (Eq. 3) for a full exploration of the solution
space. For direct analysis of sparse data provided by field observations such a complete analysis is, however, not appropriate
and simplifications need to be introduced.

In order to do so we need to perform laboratory experiments with analogue materials to gain insight into the timescales. For
such experiments, we may switch from a chemical perspective with fluxes of species to a mechanical viewpoint represented
730 by strain and strain rates. Both can be coupled through an equation of state approach and mixture theory as discussed in part
I (Regenauer-Lieb et al., 2021). Another approach is to jump from the meso-scale simulation directly to the continuum scale
through the introduction of an internal variable and the assumption of local equilibrium. This approach is also known as or
thermodynamics of internal variables (Maugin and Muschik, 1999; Jacquey and Regenauer-Lieb, 2020). We will discuss both
approaches in the next section.

735 3.1 Diffusion waves at mechanical scale

Oscillatory [propagating](#) deformation bands are well documented in deformation experiments of plastic materials such as steel.
Perhaps the most well-studied effect is the development of characteristic Portevin-Le Chatelier (PLC) bands which show
rhythmic bands of volumetric strain in metals deformed under tensile conditions. The banding is attributed to a damped runaway
effect induced by a critical (negative) strain-rate sensitivity (Zaiser and Hähner, 1997). In PLC the transition from smooth to
740 oscillatory deformation is understood as a critical point phenomenon where mesoscopic fluctuations manifest themselves at
the macro-scale due to strain-rate softening. [This approach is similar to the spring-slider model discussed earlier for modelling
earthquakes. A recent discussion of the PLC bands modelled by an alternative nonlocal internal length gradient approach is
presented in Aifantis \(2021\).](#)

A comprehensive review of theoretical approaches to model the phenomenon of an oscillatory material response of plastic
745 materials with a serrated stress-strain response (or jerky flow) can [also](#) be found in Zaiser and Hähner (1997). According
to the review, models first have been developed based on a phenomenological approach proposing that the effective stress
applied at the boundary of the deformed sample is a non-linear function of the strain rate $\dot{\epsilon}$ which can become negative. In

the following, we will ~~interpret the approach at the mechanical scale in the light of the~~ briefly discuss the metal deformation examples and the physical processes that are thought to underpin this peculiar constitutive behaviour. The physics appears to
750 rely on reaction-diffusion ~~approach and THMC coupling concerning the~~ processes that in fact can be described by an excitation wave phenomenon of the FKPP-type (Zuev and Barannikova, 2010). We also present observation of diffusion waves in rock analogues which are perhaps more relevant to the earthquake application.

3.1.1 Oscillatory deformation bands in plastic deformation of materials with internal structure

The phenomenological approach where the effective stress weakens with increasing strain-rate is ill-posed as it leads to a
755 runaway effect when a small local perturbation in strain-rate grows without bounds in an ever-increasing manner. Various approaches have been proposed to address this problem. In the context of relating the phenomenological approach to a physics-based model, the most interesting approach is the one by Estrin and Kubin (1995). The authors proposed to regularise the ill-posed localised runaway strain by introducing a pseudo-diffusivity; the function that was proposed as an extension of Orowan's equation is

$$760 \quad \dot{\varepsilon} = b\rho_m v_d + D\nabla^2\varepsilon, \quad (8)$$

where b is the Burgers vector, ρ_m the dislocation density, and v_d the dislocation velocity and D a diffusivity of the strain ε . This heuristic approach was later shown to be ~~resolved as~~ the 1-D solution obtained from the coarse-graining of the time-evolution gradient flow dynamics of dislocations which results in a fractional reaction-diffusion equation (Monneau and Patrizi, 2012). The well-studied jerky flow phenomenon associated with PLC band formation is now understood as the result of initially
765 independent, statistically distributed ~~meso-scale~~ nonlocal-scale dislocation mills ultimately coalescing and propagating into a macroscopic band. The best analysed mechanism for these mesoscopic fluctuations is dynamic strain ageing which gives rise to an additional characteristic retardation time scale to dislocation glide. Dynamic strain ageing operates by diffusing atoms (solute clouds) that pin dislocations and temporarily arrest the glide dislocation segments. Therefore, the plastic strain rate cannot respond instantaneously to changes of the stress, and a meso-scale diffusion length/time scale emerges which stabilises
770 the slip. The key to the oscillatory behaviour is the opposite strain-rate softening effect where the effect of retardation by diffusion is overcome through the increased mobilisation of additional dislocations (increasing the reaction rate) aided by thermal activation, hence increasing the disorder and thereby the average flow stress (Zaiser and Hähner, 1997). A similar effect of competing reaction-diffusion processes has been found in many other materials such as metal alloys (Brechet and Estrin, 1996) and self-oscillating polymer materials (Masuda et al., 2016).

775 In an elegant discourse about possible earthquake nucleation mechanisms, Orowan (1960) postulated that earthquakes may indeed be triggered by the equivalent effect of an oscillatory response of creeping rocks at depth in the crust or mantle. Orowan (1960) drew the analogy of creep failure of an annealed steel where the stress oscillates between upper and lower yield stress forming oscillatory bands called "Lüders" bands. Plastic materials, in general, are capable of arresting such small-scale fluctuations when slip tends to localise the meso-scale flow localisation and strain hardening ensures that the instability
780 mechanism cannot go catastrophic. Orowan (1960) appealed therefore to the synchronising effect of thermal feedback at depths

in the Earth's mantle where self-acceleration of creep is conceivable through an avalanche-like increase of deformation where shear heating occurs faster than conduction of heat [away](#) from the shear plane, finally resulting in a localised melting event as an earthquake instability.

While runaway melting instabilities have indeed been postulated as a possible source mechanism for extremely deep earthquakes such as the 1994 great Bolivian earthquake (Kanamori et al., 1998), the mechanism may be considered ~~an~~ [end-member-another extreme end member of earthquake mechanisms in addition to the one proposed for ETS sequences \(Poulet et al., 2014b\)](#). Kanamori and Brodsky (2001) proposed that there are a great number of other possible earthquakes micro-instabilities without invoking a melting instability, however, the critical aspect remains to identify the physics of connecting small and large scales. If we consider THMC feedback as a source mechanism for earthquakes, we conclude that the largest scale coupling effect is again the temperature. This becomes obvious from inspecting Table 1 [in the appendix](#) where the thermal diffusion process defines the largest diffusional length scale. Thermal coupling is so efficient that a material can be considered macroscopically homogeneous and at thermostatic equilibrium, while at the mesoscopic scale it still shows widespread thermal fluctuations. If we refer again to the PLC-effect as an analogy of a thermally activated material it has been recognised that these statistically uncorrelated fluctuations may, for certain critical conditions, be coordinated in the shape of a thermal wavefront that propagates through the material (Zaiser and Hähner, 1997). These wavefronts are typical acceleration waves illustrated in Fig 4 of [part-Part 1](#) (Regenauer-Lieb et al., 2021). While metals and rocks at depth are thermally activated materials, we need to discuss acceleration waves in brittle materials where the thermal activation process is less obvious.

3.1.2 Compression of rocks and rock analogues in the laboratory

Crushable granular materials show a similar strain-rate weakening behaviour as metals. This effect may lead to the phenomenon of propagating compaction waves in crushed snow (Barraclough et al., 2017) and puffed rice (Guillard et al., 2015) where ~~excellent experiments are available~~ [the propagation of compaction waves is well documented](#). The generic experimental configuration is shown in Fig. 4. Travelling compaction waves that reflect from ~~the boundaries~~ [boundaries or release their energy by acoustic emission at the top boundary](#) have been recorded by optical [and acoustic](#) means (Guillard et al., 2015; Barraclough et al., 2017). [The puffed rice experiment is an excellent illustration of diffusion waves that can be easily replicated for demonstration purposes \(Fig. 5\)](#). Experiments have also been performed by partially soaking the puffed rice at the bottom of the experimental setup (Einav and Guillard, 2018). The interference of the compaction in unsaturated compaction and capillary-driven crushing of the puffed rice led to oscillatory catastrophic events of global compaction with acoustic-emissions perceptible as loud audible beats termed "rice-quakes" by the authors (Einav and Guillard, 2018).

An important aspect of the interpretation of the laboratory experiments is that, when going from a perspective of propagating chemical or thermal acceleration wavefronts to a recording of the mechanical response of the medium, a coarse-graining step is made. We are, therefore, in most cases, not able to record the expected individual multiscale THMC wavefronts but are more likely to record the cumulative, convolved effect of the waveforms that underpin and support the mechanical deformation that can ultimately lead to macroscopic failure. From a mechanical perspective, we encounter two different dynamical regimes: in the first regime the dynamics of chemical, hydraulic, elastodynamic mechanical, and thermal wavefronts is still important, and




Figure 4. Experimental setup for crushing a granular strain-rate weakening medium. (a) The problem is here formulated in analogy to the Terzaghi consolidation problem where a pore-filling fluid is diffusing out of the compacting region and crushed grains (solids) are replacing the collapsed pores. The meso-scale (b) and (c) illustrate the nonlocal mesoscale process is sampled by a wave-scale Representative Elementary Volume (REV). The cross-diffusion of the solid into the fluid phase leads to an increase in density, hence an increase in fluid pressure through the equation of state. The reciprocal cross-diffusion of fluids into the solid skeleton leads likewise to an increase in solid pressure assuming that the deformation of the solid is constrained. The macro-scale continuum-scale REV for a thermostatic formulation is defined in Fig. 2. The dependence of the registered wave speed on the applied boundary velocity is here suggested to be a possible diagnostic tool to differentiate between the thermostatic end-member and the full thermodynamic meso-scale formulation of the problem.

815 the system cannot be simplified by a thermostatic assumption. The other regime is where the thermostatic assumption holds, and the problem can be described by a quasi-static framework, where the time dependence of the system can be neglected and the problem reduces to an ideal plastic time-independent one, only controlled by the kinematic boundary conditions, e.g. the position of the porous ceramic platen applying the compression in Fig. 4.

The thermomechanical theory of internal variables (Maugin and Muschik, 1999) is a variance of classical plasticity theory
820 as it allows for additional time-dependent processes describing the evolution of local thermostatic equilibrium states through internal state variables. The introduction of additional time-dependent processes leads to a relative difference from the ideal plastic kinematic reference frame, and the localisation band can move with respect to the static, ideal plastic solution which is fixed concerning the kinematic boundary conditions in a self-similar way. We can identify the two theoretical end-member cases by recording the dependence of the velocity of the optically recorded compaction waves on the velocity applied to the boundary
825 of the experiments. If there is a positive correlation with the velocity applied to the boundary, the thermostatic end-member applies (Barracough et al., 2017). Whereas if the velocity of the wave proves to be a material constant and independent of the




Figure 5. Recreation of Guillard et al. (2015) experiment with puffed rice. (a) time-space plot averaged over a horizontal cross-section of the tube showing compaction waves travelling at less than 1mm/s up and down the tube. The overlay shows the axial stress-strain curve where stress drops correspond to nucleation of new compaction bands at the bottom of the rice pack; (b) snapshots of the compressed puffed rice at 0%, 8%, 16%, 24%, 32%, 40%, 48%, 56%, 64% and 72% axial strain (from left to right). At the termination of the experiment the rice pack is reduced to powder.

boundary velocity, the dynamic solution applies. ~~This property can be used as a diagnostic tool for determining dissipative material properties as described in the appendix.~~

4 Application to earthquake physics

830 Theoretical approaches to the physics of earthquake instabilities originally were conceived as a shear instability on a frictional sliding surface (Brace and Byerlee, 1966). The role of pressure on the dynamics of the slider was derived empirically by laboratory experiments defining a rate-and-state variable friction law (Dieterich, 1972, 1987; Ruina, 1983; Tse and Rice, 1986; Rice et al., 2001). Instabilities through shear heating feedback were later considered to play an important role (Ogawa, 1987; Regenauer-Lieb and Yuen, 1998; Braeck and Podladchikov, 2007). Additionally, a thermally induced fluid pressurization term
 835 was found to be an important component for accelerated creep (Vardoulakis, 2001; Rice, 2006). Another important ingredient of

the earthquake instability was thought to be the coupling of scales, where at least two different processes, operating at different time and length scales, interact (Ohnaka, 2003). The approach presented here summarizes these effects in the diffusion matrix \tilde{D}_{ij} (Eq. 6) and enables upscaling via renormalization group theory (Regenauer-Lieb et al., 2013b; Hanasoge et al., 2017).

4.1 ~~Cross-diffusion waves~~The effect of cross-diffusion

840 A fully populated diffusion matrix provides the opportunity to extend the postulate of coupling different scale processes in earthquake mechanics (Ohnaka, 2003). ~~Cross-diffusion, in excitable media (Molotkov and Vakulenko, 1993). For the mathematical discussion we consider a poromechanical formulation introduced earlier (Hu et al., 2020) which describes cross-diffusion between solid and fluid particles as illustrated in Fig. (4). Of particular interest for the earthquake problem is whether the hydro-mechanically coupled cross-diffusion can lead to the formation of self-supporting standing wave solutions (Berenstein and Beta, 2017).~~
845 ~~The integrable focusing non-linear Schrödinger equation bears similarities but a standing wave of significant amplitude as observed in other fields (Berenstein and Beta, 2012). In order to investigate whether cross-diffusion waves describe a much broader class of waves and hence offer a richer solution for real-life applications (Tsyganov and Biktashev, 2014). It is, however, difficult to derive exact analytical propagating wave solutions of the cross-diffusion-wave phenomenon. The piecewise linearised FitzHugh-Nagumo oscillator (Zemskov et al., 2017) is by far the best analysed prototype of a cross-diffusion wave triggered by an excitable system with short lived spikes and a slow recovery. The FitzHugh-Nagumo cross-diffusion model has originally been developed to describe the propagation of electrical impulses in nerves (Antonioletti et al., 2017).~~
850 ~~can lead, for certain parameters, to a sharp concentration of wave energy into a single short-lived spike we follow a recent generalisation of the original formulation of Hu et al. (2020), which allowed a linear stability analysis as well as a numerical assessment of the parametric space presented elsewhere (Sun et al., 2021). The article including the supporting numerical code are available as a preprint on the Earth and Space Science Open Archive (ESSOAr).~~

855 ~~We use a generic application of this oscillator to illustrate the potential feedback of just two THMC processes and the conditions that may prepare the formation of a future fault plane. The real waveforms of the transient~~
~~Before discussing the significance of the results for the earthquake problems we summarise briefly the rationale for the choice of the particular reaction-cross-diffusion equation. The generic type of reaction- cross-diffusion waves are expected to be more complex,~~
860 ~~equation for a fully saturated hydromechanically coupled porous medium has been introduced by (Hu et al., 2020):~~

$$\frac{\partial \bar{p}_s}{\partial t} = D_M \frac{\partial^2 \bar{p}_s}{\partial x^2} + d_H \frac{\partial^2 p_f}{\partial x^2} + R_1,$$

$$\frac{\partial p_f}{\partial t} = d_M \frac{\partial^2 \bar{p}_s}{\partial x^2} + D_H \frac{\partial^2 p_f}{\partial x^2} + R_2,$$

865 ~~where D_H and further work is required for a full theoretical assessment of cross-diffusion waves (Tsyganov and Biktashev, 2014). We, therefore, present only a high-level application of wave solutions to transfer knowledge from other disciplines to this new field of research (e. g. mathematical biology, computational chemistry, ocean and ice waves, D_M are the solid and fluid pressure self-diffusion coefficients and d_H and photonics). We use analytical solutions developed in these fields, supplemented~~

by our long-wavelength solution for the hydromechanically coupled case (Veveakis and Regenauer-Lieb, 2015). This case is currently being analysed in detailed laboratory experiments for testing the prediction of the d_M are the corresponding cross-diffusion wave hypothesis. We, therefore, restrict ourselves here only to schematic illustrations and focus on an in-depth discussion of how the cross-diffusion concept may be applied to the earthquake phenomenon. coefficients. Following the discussion on nonlocality in the diffusion explained in the introduction we also acknowledge a nonlocal coupling of the reaction as shown in the inset in Fig. 4. The specific source term for fluid pressure is assumed to be a simple linear combination of the decomposing solid and the fluid pressure production rates $R_2 = a_{21}\bar{p}_s + a_{22}p_f$, with a_{21} and a_{22} the respective rate constants. In geomechanical laboratory experiments the solid matrix is known to respond to external forces by a nonlinear reaction commonly expressed in a power law which serves as a source term for generating excitation self-diffusion waves in the characteristic earthquake example discussed earlier (Poulet et al., 2014b). In order to generalise the approach we expand the pressure reaction rate R_1 in a power series truncated at third order $R_1 = a_{11}\bar{p}_s + a_{12}p_f + a_{13}\bar{p}_s^2 + a_{14}\bar{p}_s^3$. Third and higher order reactions were found to be necessary to sustain excitation waves. We introduce following dimensionless parameters:

4.1.1 Cross-diffusion waveforms

THMC cross-diffusion waves discussed in this work stem from multiscale fluctuations as possible wave sources with the superposition of multiple waves in a wide frequency spectrum. The convolution of these waves results in interesting dispersion patterns that bear similar characteristics to quasi-solitons encountered in optical systems where chromatic dispersion is strong leading to anomalous dispersion patterns that, unlike solitons, come in discrete portions (Paschotta, 2008). Quasi-solitons encountered in photonics have two oscillating tails, one going to the left with a different wavenumber to the one going to the right. If the amplitudes of the tails are small, quasi-solitons can be treated as slowly decaying real solitons which lose their energy by radiation to form the tail (Zakharov et al., 2004).

$$\begin{aligned} \tilde{t} = \dot{\epsilon}_0 t, \tilde{p}_f = \bar{p}_f / p'_{ref}, \tilde{p}_s = \frac{\bar{p}_s}{p'_{ref}}, \tilde{x} = \frac{x}{l_0}, \tilde{D}_M = \frac{D_M}{l_0^2 \dot{\epsilon}_0}, \tilde{d}_H = \frac{d_H}{l_0^2 \dot{\epsilon}_0}, \tilde{a}_{11} = \frac{a_{11}}{\dot{\epsilon}_0}, \tilde{a}_{12} = \frac{a_{12}}{\dot{\epsilon}_0}, \tilde{a}_{13} = \frac{a_{13} p'_{ref}}{\dot{\epsilon}_0}, \\ \tilde{a}_{14} = \frac{a_{14} p'_{ref}{}^2}{\dot{\epsilon}_0}, \tilde{d}_M = \frac{d_M}{l_0^2 \dot{\epsilon}_0}, \tilde{D}_H = \frac{D_H}{l_0^2 \dot{\epsilon}_0}, \tilde{a}_{21} = \frac{a_{21}}{\dot{\epsilon}_0}, \tilde{a}_{22} = \frac{a_{22}}{\dot{\epsilon}_0}, \end{aligned} \quad (10)$$

A classification of the solution of equation (6) for the more complex discussed case of cross-diffusion has been presented recently (Tsyganov and Biktashev, 2014), and a broader definition of the where $\dot{\epsilon}_0$ denotes the reference strain rate, p'_{ref} the reference stress and l_0 the reference length. As we use the Perzyna overstress formulation (Perzyna, 1966) the reference strain rate is the background strain rate post yield, the reference stress the yield stress and the reference length determines the size of the material that has yielded. The dimensionless equation then becomes:

$$\frac{\partial \tilde{p}_s}{\partial t} = \tilde{D}_M \frac{\partial^2 \tilde{p}_s}{\partial \tilde{x}^2} + \tilde{d}_H \frac{\partial^2 \tilde{p}_f}{\partial \tilde{x}^2} + \tilde{a}_{11} \tilde{p}_s + \tilde{a}_{12} \tilde{p}_f + \tilde{a}_{13} \tilde{p}_s^2 + \tilde{a}_{14} \tilde{p}_s^3, \quad (11a)$$

$$\frac{\partial \tilde{p}_f}{\partial t} = \tilde{d}_M \frac{\partial^2 \tilde{p}_s}{\partial \tilde{x}^2} + \tilde{D}_H \frac{\partial^2 \tilde{p}_f}{\partial \tilde{x}^2} + \tilde{a}_{21} \tilde{p}_s + \tilde{a}_{22} \tilde{p}_f, \quad (11b)$$

895 4.1.1 Three different fundamental wave solutions and the long wavelength cross-diffusion limit

Depending on the parameters chosen the solution space presented in Sun et al. (2021) recovers three fundamentally different types of excitation waves which are Turing patterns, Hopf bifurcations and quasi-soliton ~~wave has been adopted to cover the richer field of wave interactions encountered in nature. Quasi-solitons feature complex dispersion relationships, where the wave velocity of individual waves (phase velocity) have a different velocity to their smooth envelope wave groups (group velocity).~~
 900 ~~This leads to dominant wave packet solutions akin to envelope solitons in the nonlinear waves.~~

(i.) Turing patterns appear because around the bifurcation point in the reaction-self-diffusion system, linearly unstable eigenfunctions exist that grow exponentially with time. While analytical solutions can be obtained using the Weierstrass functions the numerical solution is traditionally difficult. To regularize the problem, finely tuned non-linear terms need to be introduced in the reaction-diffusion equation (such as in the nonlinear Schrödinger equation ~~shown to be similar to the linear cross-diffusion equation in equation (6) (Tsyganov and Biktashev, 2014). They differ, however, from equation discussed later) or, more conveniently as is done in our approach (Sun et al., 2021) linear cross-diffusion-like terms need to be considered in a coupled system of equations.~~ THMC-Turing patterns are indeed the most obvious patterns that have been postulated in the ~~classical soliton solution in that the shape and speed of such waves in the established regime do not depend on initial and boundary conditions and are fully determined by the material parameters of literature on wave-like earth instabilities~~
 910 ~~(Ball, 2012). The framework developed here offers an ideal tool for inversion of the medium that they travel through. effective self-diffusion THMC coefficients and their implicit reaction rates. Interpreting geological structures in terms of these process parameters may allow identification of principal processes underpinning the earthquake mechanism. A first attempt has been made to derive the self-diffusion coefficients of the Turing-style structures shown in Fig. 3 Part 1 (Regenauer-Lieb et al., 2021) from field observation but the use of the 1-D approach has been unsuccessful so far (Elphick et al., 2021).~~

915 ~~Wave-packet~~ In terms of earthquake physics Turing patterns presumably only play a minor role as they are slow deformation features that require long geological times to form a stationary in space and time deformation pattern. Due to their longevity and periodicity they cannot focus wave energy into a sharp single transient event. Their role for earthquake instabilities is to create heterogeneities that may be picked up by subsequent failure mechanisms.

(ii) For the suggested reaction-cross-diffusion in equation 11 the broadest parameter space is covered by waves having
 920 discrete frequency content with logarithmic decaying amplitude for higher frequencies (Hopf bifurcations). In our simulations (Sun et al., 2021) these waves nucleate from small perturbations on the (elastic-plastic) model boundary and propagate dynamically to the opposite boundary at distance l_0 where their energy is absorbed. They can obtain a stable orbit (supercritical Hopf) leading to cumulative damage on the opposite boundary including logarithmically spaced (i.e. narrowing) compaction bands

925 towards the opposite boundary. Hopf bifurcations are perhaps the most prominently discussed candidates for earthquake source
mechanism in e.g. spring-slider models (Gu et al., 1984). Our results suggest that supercritical Hopf bifurcations are likely to
prepare a given internal structure for failure. Such a boundary may be a pre-existing fault which would correspond to the
opposite boundary separating an elastic domain from a domain yielding under the background strain rate. In the context of
the above discussed laboratory experiments Hopf bifurcations may also explain the acoustic bursts reported in the puffed rice
compression experiment (Guillard et al., 2015). However, Hopf bifurcations themselves do not have the capacity to enhance
930 the amplitude of a given excitation wave over the initial excitation amplitude as they do not have the capacity to sample energy
from the environment. The only way to amplify the magnitude of a Hopf-wave is to have two waves collide. In this case the
peak magnitude is simply the sum of the two waves.

(iii) The third class of waves that is recovered from Eq. (11) is the quasi-soliton solution that has been introduced in Part
1 (Regenauer-Lieb et al., 2021). It is encountered for very small fluid (or crushed rock) production rates which should be
935 observed under slow loading conditions such as geodynamic loads. The quasi-soliton wave reflects from boundaries often
changing and reforming after reflection on boundaries or collision with other waves. The quasi-soliton wave has been identified
as a new class of waves (Tsyganov et al., 2007).

For the classification of the quasi-soliton solution of equation 11 we follow a systematic study by Tsyganov and Biktashev (2014)
, who used the analogous FitzHugh-Nagumo equation to study the solution space. A typical feature of quasi-solitons is that
940 wave-packet solutions emerge when the wave energy is concentrated around a finite wavenumber. When the dispersion is
weak, the envelope travels with an approximately a uniform group velocity. Linear cross-diffusion can create strong non-linear
dispersion, where - depending on the coefficients - three different wave types have been classified: (1) fixed-shape propagat-
ing waves, (2) envelope waves, (3a) multi-envelope waves, and (3b) intermediate regimes appearing as multi-envelope waves
propagating as fixed shape most of the time but undergoing restructuring from time to time (Tsyganov and Biktashev, 2014).

945 The collisional behaviour of these classes of cross-diffusional waves is complicated. When ~~the cross-diffusion a quasi-soliton~~
wave hits an interface (including another ~~cross-diffusion quasi-soliton~~ wave) the amplitude of the quasi-soliton changes,
and there is a temporary diminution of the amplitude or in extreme cases an annihilation. In most cases, they recover their
original form gradually. This is another feature that is different from true solitons which do not change on impact. In two-
dimensional systems, additional complexities arise as they can penetrate, break apart on collision, or reflect into different
950 directions (Tsyganov and Biktashev, 2014). Zakharov et al. (2004) compare quasi-solitons with unstable particles in nuclear
physics. This describes their behaviour on collision but does not capture their capability to coordinate ~~into standing waves~~
on long time scales (Regenauer-Lieb et al., 2021). We propose that constructive collision of these waves may, in geological
applications, lead to the bar code imprinted in the damage zone of seismogenic faults ~~wave energy into a standing rogue~~
wave (Regenauer-Lieb et al., 2021). Before discussing the formation of a rogue wave it is useful to have a closer look at the
955 cross-diffusion waveforms.

4.1.2 Quasi-soliton waveforms, wavenumber and short wavelength amplitude magnification

THMC quasi-soliton waves discussed in this work stem from multiscale fluctuations as possible wave sources with the superposition of multiple waves in a wide frequency spectrum. The convolution of these waves results in interesting dispersion patterns that bear similar characteristics to quasi-solitons encountered in optical systems where chromatic dispersion is strong leading to anomalous dispersion patterns that, unlike solitons, come in discrete portions (Paschotta, 2008). Quasi-solitons encountered in photonics have two oscillating tails, one going to the left with a different wavenumber to the one going to the right. If the amplitudes of the tails are small, quasi-solitons can be treated as slowly decaying real solitons which lose their energy by radiation to form the tail (Zakharov et al., 2004).

Of specific interest for the earthquake problem is the aspect of the fate of the accelerations carried by the waves as discussed in Part 1 (Regenauer-Lieb et al., 2021) for cases where the wave collides and collapse after the collision. ~~In experiments carried out with collapsing puffed rice particles (Guillard et al., 2015) cross-diffusion waves were detected (Hu et al., 2020) which release an acoustic emission when annihilating after collision with the top surface. We propose that for a homogeneous plastic zone as shown in Figure (??), the first wave collisions on the symmetry axis of the future fault plane converts the energy loss of the cross-diffusion wave into local material damage that will act as a seed to future wave interactions and systematically grows the fault. For the case of heterogeneous materials, the collision of cross-diffusion waves with internal or bounding material surfaces would cause an alternative seed for the nucleation of earthquakes.~~

Another important aspect is the cross-scale coupling of the full spectrum of diffusion waves which may be seen as an energy cascade from extremely short wavelength chemical ~~cross-diffusion-quasi-soliton~~ waves to the longest wavelength which in most cases is modulated by the thermal and mechanical diffusion length scale as shown in ~~Table 1. the Table 1 of the appendix.~~ The spectral content of THMC wave interactions is extremely rich, and we have emphasized in Part 1 (Regenauer-Lieb et al., 2021) that it is perhaps best compared to a convolution sharpening filter for cases of instabilities where wave energy focusses on specific locations (Regenauer-Lieb et al., 2021).

The ~~wavelength of chemical cross-diffusion waves is relatively short and because of their rapid decay, the cross-diffusion waves emanating from either side of the elastoplastic boundary may never collide in the centre. The largest wave energy that can be transferred by cross-diffusion waves into the future fault plane is expected when the entire THMC sequence cross-diffusion phenomenon is triggered over eight to nine orders of magnitude for serpentinite-ETS instability which can be modelled by the Lotka-Volterra type model (Poulet et al., 2014b).~~

wavenumbers of the quasi-soliton waves are controlled by the competition of the diffusion processes determining the diffusion length and number of possible oscillations per unit length. The 1-D linear stability analysis for just two coupled reaction-diffusion equations discussed in Sun et al. (2021) illustrates the role of the wavelength (or its inverse the wavenumber) for the nucleation of quasi-soliton waves. The linear stability analysis (Sun et al., 2021) shows that cross-diffusional wave nucleate if \tilde{d}_M and \tilde{d}_H are nonzero, of opposite sign and sufficiently large to overcome the self-diffusion processes in the first term, which is always positive.

4.1.3 ~~Cross-diffusion collisions~~

990 ~~In the context of an earthquake instability,~~ The instability criterion also suggests a critical lower limit k_{min} (longest wavelength) for which no quasi-soliton wave can nucleate as the self-diffusion term becomes dominant. This minimum wavenumber (longest wavelength) can be constrained further by the system size. We argue that longest wavelength is a fraction of the system size, defined by long-wavelength solution (Regenauer-Lieb et al., 2013a; Veveakis and Regenauer-Lieb, 2015) where the cross-diffusion coefficients are adiabatically eliminated. This is the Turing style long-wave soliton solution that turns cross-diffusional waves into a standing wave Korteweg de Vries-type cnoidal solution in normal resonance mode.

995 For investigating the opposite scenario where shorter wavelength cross-diffusional waves might cascade to a small dispersion limit of a coordinated ~~long-wavelength~~ short time-scale instability around a dominant ~~wavenumber~~ small wavelength with a maximum amplification factor $R(k)$ (see Eq. ??). ~~Recently, a~~ we look at an idealised solution where we assume that there is no self-diffusion and the equation 11 is only controlled by cross-diffusion. For further simplification we normalise both cross-diffusion coefficients to unity. We also use the compact form of the Kramers-Kronig relationship and test the solution by a perturbation new complex wave function $\psi = \tilde{p}_s - i\tilde{p}_f$. In summary we investigate following parameters:

$$\begin{aligned} \psi &= \tilde{p}_s - i\tilde{p}_f, & \tilde{D}_M &= \tilde{D}_H = 0, & \tilde{d}_H &= -\tilde{d}_M = 1 \\ \tilde{R}_1 &= \tilde{p}_f (\tilde{p}_s)^2 + (\tilde{p}_f)^3, & \tilde{R}_2 &= -(\tilde{p}_s)^3 - \tilde{p}_s (\tilde{p}_f)^2 \end{aligned} \quad (12)$$

For these parameters our reaction-cross-diffusion equation becomes the integrable nonlinear Schrödinger equation.

$$i \frac{\partial \psi}{\partial t} + \nabla^2 \psi + \psi |\psi|^2 = 0 \quad (13)$$

1005 The cross-diffusion equation then is analytically tractable and as the solution relevant for nucleation of earthquakes we obtain the Peregrine soliton with a simple solution for the lowest order given by Peregrine (1983) as:

$$\psi(x, t) = \left[1 - \frac{4(1 + 2it)}{1 + 4xi^2 + 4t^2} \right] e^{it} \quad (14)$$

This classical rogue wave soliton solution features a self-focussing wave that appears from low background oscillations for $t < 0$ and suddenly reaches a peak at $x = 0$ and $t = 0$ and vanishes quickly into the background noise. The criticality condition for the Peregrine soliton requires the wavelength of the background perturbation to be very large which has been used as an argument to forecast Peregrine solitons simply by the absence or presence of such long wavelength perturbations in measurement of wave spectra (Shrira and Geogjaev, 2010). This criticality condition also shows that the Peregrine soliton achieves maximum spatial and temporal compression of wave energy by sampling energy from the far field. Its peak intensity is 9 times the background value. A numerical simulation of the wave is shown in Fig. 6. The Peregrine soliton solution is the simplest rogue wave that stems from the physics of cross-diffusion.

1015 The Peregrine soliton is by no means the only rogue wave phenomenon that stems from the nonlocal cross-diffusion terms in the nonlinear Schrödinger equation. A higher order cascade mechanism for coupling seven orders of the length scale of quasi-solitary waves has for instance been discovered in the analogous problem of rogue waves in optical fibres (Eberhard et al.,

2017a). This resonant-like scattering mode ~~may arise through incident~~ has been argued to arise through inelastic collision
1020 of cross-diffusional waves colliding with other or reflected cross-diffusional waves in a finite width around the future fault
~~core. On the grounds of the above theoretical considerations, we postulate a series of evolutionary steps that may lead to a~~
~~macro-scale rogue-wave earthquake instability. These are:-~~ Eberhard et al. (2017a) numerically investigated higher nonlinear
terms in the Schrödinger equation and found a similar criticality condition as for the simple Peregrine rogue wave. In the
1025 numerical experiments the emergence of the rogue wave is always preceded by a period of reduced short wavelength amplitude
described as a "calm before the storm".

Since the theoretical discovery of the rogue wave phenomenon in optics and hydrodynamics there has now been ample proof
of their existence in controlled experiments. Solli et al. (2007) has provided high resolution measurements of optical rogue
waves with picoseconds resolution and Dudley et al. (2019) have provided a rigorous comparison and review of rogue waves
in fibre optics and rogue waves in hydrodynamic tank experiments. Although the media that the waves are travelling through
1030 are completely different the basic phenomenon is identical. We propose here that rogue waves stemming from cross-diffusion
terms and quasi-soliton collisions in hydromechanically coupled media of the solid earth provide a source mechanism for
earthquakes.

5 Discussion and conclusions

We have introduced a new approach to THMC instabilities using the concept of cross-diffusion. To simplify the application,
1035 we have so far only focussed on dissipative cross-diffusional P -waves. We may now discuss the inclusion of cross-diffusional
 S -waves and speculate about the interaction with the P -waves. We have shown in Part 1 (Regenauer-Lieb et al., 2021) that the
wave equations can be decomposed by using the Helmholtz decomposition of the equation of motion, into P - (compressional)
and S - (shear) ~~cross-diffusion~~ quasi-soliton waves. The analysis suggests that cross-diffusion provides a crucial link to allow
cross-scale coupling of the multiphysics processes potentially leading to earthquake instabilities. For critical cross-diffusion
1040 coefficients and associated reaction terms, a bi-directional energy cascade of acceleration cross-diffusion P -waves, from small
scale thermo-chemical (TC) and chemo-mechanical (CM) dissipative waves to meso-scale hydro-mechanical (HM) dissipative
waves, can be triggered by a geodynamic driving force. This in turn may nucleate ~~shear-cross-diffusion~~ shear-quasi-soliton
waves in the form of a thermo-mechanical (TM) shear-wave instability.

~~The multiscale THMC-waves initially are low-energy release volumetric diffusion P -waves shown in Step 2 (Fig. ??) and~~
1045 ~~are free of kinetic energy, but if they trigger thermo-mechanical~~ We have also presented a derivation of the Peregrine soliton
solution as the extreme short-wavelength standing wave end-member of the cross-diffusion shear-waves (diffusion S -waves);
~~they can tap into a significant portion of the stored elastic energy around the fault. This process may, for a critical set of~~
~~reaction-diffusion parameters, ultimately lead to a substantial energy release sufficient to communicate via cross-diffusion~~
~~with their elastic counterparts (Cartwright et al., 1997), and an earthquake instability occurs. The rogue cross-diffusion P -~~
1050 ~~wave may thus be understood as a trigger to lubricate the earthquake fault. The cross-diffusion S -wave may by itself develop~~
~~a similar cascade of energy and create its rogue wave, which is the earthquake instability itself.~~




Figure 6. Proposed earthquake cycle: Step 1) The size Numerical calculation of the plastic zone is dependent on Peregrine soliton using the boundary conditions and the micro-physics accommodating plastic deformation. We assume in our discussion that the zone is deforming pervasively by a power-law. Step 2) For critical conditions ($R(k) > 0$) excitable self-oscillatory cross-diffusion waves propagate from opposite sides towards the future fault plane. Here, we use the analytical solution approach of the piecewise linear approximation of the FitzHugh-Nagumo cross-diffusion wave (Zemskov et al., 2017) for illustration. A snapshot is shown just before the collision on the future fault plane. The pressure wave of the two phases C_1 (fluid, black) Yang (2010) and C_2 (solid, blue) is shown in the graph Ward et al. (2019). The collision of the waves can lead to solution is an extreme sharpening end-member short wavelength, short timescale compression of the waveform collecting wave power over eight to nine orders of magnitude into a rogue wave event energy $|\psi|^2$. Step 3) Rogue wave event on In the Draupner Platform in the North Sea (Cavaleri et al., 2016). Step 4) The cross-diffusion waves can turn into real solitons if the amplitude context of their radiative tails becomes vanishingly small. This situation may follow the rogue wave event during relaxation or during prolonged slow deformation without rogue wave. Under these conditions selected parameters the lowest wavenumber k_{min} resonant-like scattering P-wave mode can fully develop, and the static solution can be reduced to lower dimension by considering only the self-diffusion coefficients. A very simple solution soliton is the Korteweg-de Vries equation (Regenauer-Lieb et al., 2013a; Veveakis and Regenauer-Lieb, 2015) where understood as a strictly periodic pattern of overpressured fluid channels (non-dimensional overpressure labelled pressure spike on the ordinate future fault plane that triggers the ultimate (shear) follows seismic moment release. The dynamics associated with earthquakes results, however, more likely into more complex patterns such as those described by the nonlinear Schrödinger equation. Slow deformation or slow slip events might be better candidates for the solution shown in Step 4. A good example is the periodic fracture pattern stemming from slow diagenetic reactions in unconventional shale gas basins (Albritton et al., 2017), which has been shown to be a good candidate for the solution shown in Step 4.

~~We have also presented in Step 3 (Fig. ??) the approach. The Peregrine soliton has been used to explain the~~ iconic Draupner Wave example recorded on 1 January 1995 by a downward looking laser beam on ~~the oil platform an oil platform in the North Sea~~. The exceptional nature of these rogue waves bears many similarities with earthquake events in terms of predictability. A hindcast analysis of the Draupner wave came to the conclusion that rogue waves are not predictable with current statistical means (Cavaleri et al., 2016). Records at a specific location are often misleading and the probability of detecting a rogue wave must be considered both in space and time; they have thought to be accepted as part of the reality of the ocean at a given sea state (Cavaleri et al., 2016). Recent work refutes this conclusion and raises hopes that a statistical analysis is possible based on large deviation theory combined with the simplified non-linear ~~Schrödinger~~ Schrödinger equation solution of the ~~cross-diffusion quasi-soliton~~ waves using random initial data (Dematteis et al., 2019). This ~~raises hopes may be useful~~ for earthquake research ~~but it will take some time~~, acknowledging that it took nearly 15 years of research on the Draupner Wave to come to this point. ~~To make progress on this matter, we have to leave the analytical assessment of the problem presented in this paper aside and investigate numerical solutions.~~

~~Numerical solutions of this stiff problem are unfortunately difficult, and it may be useful to consider weak formulations by a reduction procedure through adiabatic elimination of the fast cross-diffusion process into an effective cross-diffusion formulation by time integration to the slow self-diffusion time scale (Biktashev and Tsyganov, 2016). Specifically, the upsealed solutions can be regarded as long-wavelength (infinite/quasistatic time-scale limits) of the travelling cross-diffusion wave solutions. The dominant wave number is described by a critical ratio of effective self-diffusion coefficients. The relationship between the long-wavelength soliton cnoidal solution in Step 4 (Fig. ??) of~~

1070 **Appendices**

A Self-Diffusion length/time scale

~~The yardstick used to measure the length scales of diffusion fronts in reaction-diffusion equations is the diffusional length scale. Any scale that is significantly larger than the diffusional length scale is considered to be unaffected by the Korteweg-de Vries equation (Regenauer-Lieb et al., 2013a; Veveakis and Regenauer-Lieb, 2015) and the quasi-soliton solution with oscillating tails can be derived by the Jacobi elliptic functions method of solution. If the modulus of the Jacoby elliptic function asymptotically approaches zero the solutions shown in Step 4 (Fig. ??) can be obtained (Wang et al., 2018).~~ diffusion front for a given diffusion time t_d . We will later on reinterpret the diffusion length as an uncertainty measure. The characteristic diffusion length scale for a 1-D problem is:

$$\underline{L_d} \approx \sqrt{2\zeta_i t_d}. \quad (15)$$

1080 The diffusion length scale L_d allows definition of a normalised Gaussian scale space ensuring that the area under the Gaussian distribution always remains the same. The Gaussian probability density function (here called a Gaussian wavelet) is often used

in probability theory where the diffusion length is related to the standard deviation, its square to the variance and the function centroid to the mean.

<i>Self Diffusion</i>	<i>Diffusivity</i> [m^2/s]	<i>Process time</i> [s]	<i>Diffusion Length</i> [m]
ζ_T	10^{-6}	10^{12}	10^3
ζ_H	$10^{-5} - 10^{-1}$	10^2	$6 \times 10^{-2} - 6 \times 10^0$
ζ_M	<i>all</i>	<i>all</i>	<i>all</i>
ζ_C	$10^{-19} - 10^{-15}$	10^{12}	$6 \times 10^{-4} - 6 \times 10^{-2}$

Table 1.

Typical diffusion length scales for geological THMC processes (Regenauer-Lieb et al., 2013a). Eq. (15) is used to calculate length scales for a given reaction time. For thermal and chemical processes a geodynamic time scale of 10^{12} s is chosen. Geodynamic processes are assumed to cause fluid flow at pore level in less than 100 s. Note, the mechanical diffusion length scale can range over all time and length scales. As an example, the visco-elastic diffusion length scale for elasto-dynamic earthquake events is very short. However, prior to the catastrophic event stress diffusion can range over all scales and can couple all processes through elasto-visco-plastic creep processes.

1085 ~~The quasistatic spatially inhomogeneous solutions of Step 4 (Fig. ??) are also known as Turing patterns (Turing, 1952) – The special role of cross-diffusion for the emergence of Turing patterns is their capability to generate spatial periodicity (Berenstein and Beta, 2012), an aspect that is often overlooked in~~

A.1 Reaction-Diffusion length/time scales

1090 ~~The simple diffusion process without reaction leads to a decaying and broadening diffusion front of an initial perturbation. When considering an active source term, the solution turns into a propagating wavefront which was first discovered in 1906 by Robert Luther. An English translation of the original article appeared in the analysis of Turing patterns. The upsealed Korteweg-de Vries equation does not necessarily honour the co-dependence between the diffusion and reaction rate constants of the cross-diffusion process, and results need to be investigated with caution (Hu et al., 2020; Vanag and Epstein, 2009). Turing patterns appear because around the bifurcation point in the reaction-self-diffusion system, linearly unstable eigenfunctions exist that grow exponentially with time. To regularize the problem, finely tuned non-linear terms need to be introduced in the Journal of Chemical Education (Luther, 1987). The same phenomenon was rediscovered 30 years later and is now known as Fisher or Fisher-Kolmogorov-Petrovsky-Piskunov (FKPP) equation (Kolmogorov et al., 1937). Fisher originally discussed the reaction-diffusion equation (such as in the nonlinear Schrödinger equation) or, more conveniently, linear cross-diffusion-like terms need to be added in a coupled system of equations. We postulate here that THMC Turing patterns are indeed the multiscale patterns observed in nature (Sethna et al., 2001). They offer themselves as an ideal tool for inversion of the effective self-diffusion~~

1100 ~~THMC coefficients and their implicit reaction rates. Interpreting geological structures in terms of these process parameters will allow identification of principal processes underpinning the earthquake mechanism.~~

Further theoretical considerations on the nature of cross-diffusion waves may also help in the design and analysis of laboratory experiments. Quasi-solitons are similar to real solitons in that they can penetrate through each other and reflect from boundaries. Differences are that the amplitudes of the true solitons do not change after an impact while the dynamics of quasi-solitons on impact are often naturally seen as a temporary diminution of the amplitude with subsequent gradual recovery (Tsyganov and Biktashev, 2014). Another important difference is that the amplitude and speed of a true soliton depend on initial conditions, while for the quasi-soliton they depend on the material parameters. This property offers new avenues for earthquake physics. We are currently investigating these wave phenomena in controlled laboratory experiments and attempt to use the unique relationship of amplitude and wave speed dependence on material properties as a diagnostic tool for data assimilation equation to calculate the propagation of a mutant virus in an infinite domain (Fisher, 1937).

B Derivation of dissipative material properties from laboratory measurements

The velocity measurement in the laboratory requires an identification of a relative reference frame. When shifting from a material reference frame inside the rock formation, as discussed before, to a laboratory or field reference frame we have to consider the relative direction of the travelling wave and subtract or add the velocity vector of the boundaries of the experiment to calculate the material velocity vector of the wave from a video recording. In practice, The addition of an reactive non-linear source term (e.g. $R_i = k_i C_i (1 - C_i)$ for the Fisher-Kolmogorov equation) into the diffusion equation leads to the material wave velocity is expected to be very much faster than the background geological strain rate in the field or the velocity of the boundary, and the correction is only a minor one and may be neglected (Guillard et al., 2015). However, there exists a theoretical limit of vanishing wave speed of acceleration waves in which this is important (Barracough et al., 2017). This limit underpins the classic theory of localisation phenomena in plasticity (Rudnicki and Rice, 1975), where the acceleration wave speed is set to zero (standing soliton wave) and acceleration waves transform into stationary localisation bands. Although, as emphasized before, the comparison with conservative systems is inappropriate, we can compare this situation with a resonance phenomenon in elasticity. In the case of a diffusion wave, this situation is equivalent to the diffusion wave having the capability to retain the quickly fading information of the boundary conditions and convolve constructively with the reflected wave from the opposite boundary. This standing soliton wave solution is only possible for long wavelengths, low frequency end members due to the physics of high-frequency damping. The standing wave phenomenon is identified as the final case of a (thermostatic) travelling wave solution with zero velocity. interesting phenomenon of the generation of a self-oscillatory excitation wave, where after Fisher's work on the topic progress was mainly made in the Russian literature triggered by the seminal work of Kolmogorov et al. (1937) discussed in Fig.??.

1130 If localisation phenomena in the form of travelling waves or standing waves can be observed, a new diagnostic test for deriving dissipative material properties from laboratory experiments can be suggested. This test reveals how close the experiment is to thermostatic equilibrium. If the wave is controlled by its own dynamics and no relationship between the applied background

strain rate of the experiment (e. g. velocity of the piston) applies. In Russian literature, the wave velocity can be approximated by the square root relationship of the Fisher-Kolmogorov type (Eq. 16). The reason for the independence of dynamic waves from the boundary velocity is that the waves quickly loose the information of the initial conditions imposed by the step function applied at the boundaries of the experiment. These travelling wave solution are a new type of waves having an extremely rich dynamics. They are quasi-solitons with very different properties to the classical soliton waves (Tsyganov and Biktashev, 2014). On the other hand, term "autowave" was introduced (Ostrovskii, 2015; Molotkov and Vakulenko, 1993; Zuev and Barannikova, 2010) . The self-excitation wave constitutes a fundamental class of waves encountered in all reaction-diffusion systems in physics, biology, and chemistry (Vasil'ev, 1979). The principal difference to classical wave equations that are based on hyperbolic differential equations, is that the autowave phenomenon arises from a non-linear source term in parabolic equations.

The reaction-diffusion time-scales of a single reaction-diffusion equation can be expressed by a generalization of the Damköhler number for chemical reaction-diffusion processes to all THMC couplings. The Damköhler number describes the ratio of the diffusion over the reaction time or the equivalent ratio of the reaction rate over the considered diffusion rate. This ratio thus considers an additional rate of the chemical reaction. This is illustrated here only for an infinite autocatalytic source term in the reaction-diffusion system (Fig. ??). For a finite autocatlytic reaction the reactive source term has a growth function which is sigmoid, also called a logistic function. This means that the reactant initially grows exponentially, similar to the case of near thermostatic equilibrium, this relationship should change to a dependence on the applied boundary velocity , as the information of the applied boundary condition can spread through the sample and the diffusion wave has achieved a constructive convolution of the waves. An extreme quasi-static, thermostatic solution is shown in Step 4 (Fig. ??) where a stationary (standing) wave is shown with zero velocity. The derivation of dissipative material parameters for the zero velocity case has already been discussed (Regenauer-Lieb et al., 2013a). For the thermostatic case the wave velocity should be zero or be dependent on the boundary velocity, as discussed next. This suggested diagnostic tool opens a new way to quantify dynamic material properties and to identify how close the system is to thermostatic equilibrium. infinite source, followed by linear reactant growth and a final zero growth branch. These general solutions imply different shapes of the self-supporting propagating wave and, depending on the value of the diffusivities, also a finite life-time of the wave.

A.1 Thermostatic soliton waves

Classical plasticity theory can be extended to account for the slow dynamics before approaching the full quasi-static case. For this case, we may neglect the dynamics of forward and backward reflecting waves from the boundaries and introduce an internal state variable that captures the relaxation to quasi-static equilibrium (Jacquey and Regenauer-Lieb, 2020). The dynamics are assessed by assuming a meso-scale thermostatic equilibrium state that is linked to the next local equilibrium state by a finite-rate process slaved to the time scale of the irreversible processes (Maugin and Muschik, 1999). This is captured by the characteristic dissipative time scale of the selected internal variable α which defines the relaxation to This geologically more relevant situation is described in Molotkov and Vakulenko (1993). The authors describe generalised reaction-diffusion systems and find that the wave behaviour depends on only three parameters. For small wavefront curvature the autowave is

described by the two parameters of the infinite source term solution discussed above, while for the more general case the equilibrium of normal velocity of the time-dependent processes. This time scale may be defined as

$$t_\alpha = \frac{\alpha}{\dot{\alpha}},$$

and the velocity of the thermodynamic wave of internal variables may hence be identified as

1170
$$v_{(thermostatic)} = \frac{L_d}{t_\alpha}.$$

For the thermostatic case the experiment records a front may contain the front curvature as an additional parameter. The additional dependence of the wave velocity that is dependent on the applied boundary velocity and we can use the above discussed theory of internal variables. For this case material parameters can be derived through measuring the diffusive function on the curvature of the concentration field arises because of the fact that $\frac{\partial C_i}{\partial t}$ is proportional to the curvature of the wavefront. For regions of the wavefront where the curvature is negative the concentration must decrease at a rate proportional to the magnitude of the curvature. Conversely, the concentration must increase where the wavefront curvature is positive.

1175 Summarizing the above findings, we can now characterise the reaction-diffusion thermodynamic system by five key features: i.) a bistable or multistable (for several reactions) region with a stable stationary mode and a mode for the nucleation of propagating autowaves above a critical activation threshold; ii) in the activated state, the wavefront separates two regions, a local region characterised by the particular THMC diffusional length scale L_d affected by the reactions R_i , and a large region at $> L_d$ which is outside the reaction-diffusion wave; iii) for long time scales, the wavefield is governed by characteristic self-oscillatory motions which for bistable systems are described by just three parameters. For multistable systems chaotic oscillations are expected (Molotkov and Vakulenko, 1993). For the analysis of this complicated system we will propose to use perturbation theory and illustrate the approach through some basic concepts of signal processing. In the bistable system the Fisher-Kolmogorov wave is a self-propagation dissipative wave at a characteristic wave speed whose lower limit can be quantified by the square root of the Damköhler number times the diffusivity normalised by the characteristic diffusion length scale L_d ; (iv) the propagating wave exponentially scatters information about its initial condition, and the wavefield only carries information about the dissipative properties into the far-field; this is an important differentiation from waves in the conservative system (e.g. the thickness of the propagating compaction band) and the background strain rate as $\dot{\alpha}$ (e.g. compaction strain rate imposed on the sample by the compression piston). This interpretation assumes that all deformation activity is taking place in the active band. We can invert the magnitude of the internal variable α (e.g. elastic waves) where the wave at a long-distance still carries information about its initial conditions; (v) the compaction strain) from measuring the material speed of the propagating compaction band by using the mass conservation criterion in Eq. ???. This method of deriving the band strain in a propagating compaction band in compaction of snow has been used by Barraclough et al. (2017).

1195 We have performed a similar compaction experiment with a highly porous limestone which produces first a stationary compaction band roughly in wave speed thus becomes a fundamental material constant defined by the middle of the sample after only 3% axial strain (Chen et al., 2020). When interpreting the result in terms of a standing wave limit (zero acceleration

wave speed) we expected the location to be strictly linked to the quasi-static geometric constraints which can be either the size of the sample or an internal defect. Our time-lapse X-ray Microscopy experiment (see Chen et al. (2020) for details) revealed a local porosity variation as the initial seed of rates of the compaction band. In subsequent stages of the experiment, the stationary discrete compaction band in turn acted as the nucleation point for a compaction wave travelling downwards from the discrete band ultimately leading to full compaction of the lower part of the sample. This observation is strictly identical to the experiments performed by Barraclough et al. (2017). dissipative THMC processes as:

A.1 Dynamic quasi-soliton waves

In the case where the experiment records a wave velocity that is independent of the applied boundary velocity, we can derive the

$$v_i = 4 \frac{\zeta}{L_d} \sqrt{Da_i}. \quad (16)$$

As the spreading wavefronts are self-supporting and can propagate upwards in scale, we propose that this material velocity not only applies to the above discussed chemical reaction-diffusion equations but to all reaction-diffusion equations of the THMC-coupled system. In this proposition, the propagating multiscale and multiphysics waves provide the capacity to link the different THMC-length-scales and could explain the multifractal nature of earthquakes. The approach allows a significant simplification of the earthquake physics problem as the exponential rate of approaching the Kolmogorov limit of a self-oscillating wavefront shown in Fig. ?? for a given scale allows a characterisation of the important physics in terms of the wave velocity. With the autowave approach, one can turn any non-linear perturbation of the local source into a linear propagating waveform only governed by the dissipative material properties directly from measuring the diffusion length scale L_d and with the measured material velocity inverting Eq. 16 to obtain the effective Damköhler number Da . Alternatively, we can derive the instantaneous modulus C from inverting Eq. 7 from a measurement of the density ρ and the band velocity v . Autowaves will by themselves recover a characteristic wavefield dictated by the reaction-diffusion rate constants.

Guillard et al. (2015) have performed experiments with compacted puffed rice in a setup similar to Fig. 4 recording the alternative case of a dynamic solution. The wave speed was found to be independent of the applied boundary velocity. Guillard et al. (2015) found that, when varying the velocity by a factor of 2.5, This characteristic behaviour is used, for instance, in medicine where autowaves are encountered in many fields. The electrical nerve impulses that drive a regular heart beat are an example (Antonioletti et al., 2017). The authors describe how the characteristic recovery of the autowave waveform after a random perturbation can be used, for instance, for defibrillation strategies (a small electrical stimulus applied through a pacemaker) for treatment of life-threatening heart arrhythmia. In this sense, earthquake physics might profit from an understanding of the partial differential equations developed in mathematical biology, epidemiology (wave-like propagation of viruses) and other biomedical applications for which numerical open-source tools are available. One such tool is the "heart beat box" (Antonioletti et al., 2017) which uses a mathematical formulation of the human heart in terms of a coupled electro-mechanical reaction-diffusion equations similar to the number of propagating bands increased but not their velocity. If the density of the travelling compaction band can be measured by high-speed (Synchrotron) X-Ray-CT or radiography the

~~instantaneous modulus C can directly be inverted from the band velocity. Such a measurement could then be used to derive the effective elastodynamic modulus quantifying the visco-elasto-plastic properties of the material~~[coupled reaction-diffusion equations discussed above.](#)

6 Acknowledgments

1235 This work was supported by the Australian Research Council (ARC DP170104550, DP170104557, LP170100233) and the strategic SPF01 fund of UNSW, Sydney. We would especially like to acknowledge the thought provoking experimental work of Francois Guillard and Itai Einav, as well as Barraclough et al. which may provide a new method for identification of dissipative material parameters. Further laboratory work is urgently needed to explore this new avenue.

References

- 1240 Adomian, G.: Fisher-Kolmogorov equation, *Applied Mathematics Letters*, 8, 51–52, [https://doi.org/10.1016/0893-9659\(95\)00010-N](https://doi.org/10.1016/0893-9659(95)00010-N), 1995.
- Aifantis, E. C.: Gradient Extension of Classical Material Models: From Nuclear and Condensed Matter Scales to Earth and Cosmological Scales, vol. 1 of *Springer Tracts in Mechanical Engineering*, pp. 417–452, Springer, Zurich, https://doi.org/https://doi.org/10.1007/978-3-030-63050-8_15, 2021.
- Alevizos, S., Poulet, T., and Veveakis, E.: Thermo-poro-mechanics of chemically active creeping faults. 1: Theory and steady state considerations, *Journal of Geophysical Research: Solid Earth*, 119, 4558–4582, <https://doi.org/10.1002/2013JB010070>, 2014.
- 1245 Alevizos, S., Poulet, T., Sari, M., Lesueur, M., Regenauer-Lieb, K., and Veveakis, M.: A Framework for Fracture Network Formation in Overpressurised Impermeable Shale: Deformability Versus Diagenesis, *Rock Mechanics and Rock Engineering*, 50, 689–703, 2017.
- Amdreo-Valle, F., Mazon, J., Rossi, D., and Toledo-Molero, J.: Nonlocal Diffusion Processes, vol. 165 of *Mathematical Surveys and Monographs*, American Mathematical Society, Providence, Rhode Island, <https://doi.org/http://dx.doi.org/10.1090/surv/165>, 2010.
- 1250 Antonioletti, M., Biktashev, V. N., Jackson, A., Kharche, S. R., Stary, T., and Biktasheva, I. V.: BeatBox—HPC simulation environment for biophysically and anatomically realistic cardiac electrophysiology, *PLOS ONE*, 12, e0172292, <https://doi.org/10.1371/journal.pone.0172292>, 2017.
- Ball, P.: Pattern Formation in Nature: Physical Constraints and Self-Organising Characteristics, *Architectural Design*, 82, 22–27, <https://doi.org/10.1002/ad.1375>, 2012.
- 1255 Balluffi, R. W., Allen, S. M., and Carter, W. C.: Kinetics of Materials, <https://doi.org/10.1002/0471749311>, 2005.
- Barracough, T. W., Blackford, J. R., Liebenstein, S., Sandfeld, S., Stratford, T. J., Weinländer, G., and Zaiser, M.: Propagating compaction bands in confined compression of snow, *Nature Physics*, 13, 272–275, <https://doi.org/10.1038/nphys3966>, 2017.
- Berenstein, I. and Beta, C.: Spatiotemporal chaos arising from standing waves in a reaction-diffusion system with cross-diffusion, *The Journal of Chemical Physics*, 136, 034903, <https://doi.org/10.1063/1.3676577>, 2012.
- 1260 Biktashev, V. N. and Tsyganov, M. A.: Quasisolitons in self-diffusive excitable systems, or Why asymmetric diffusivity obeys the Second Law, *Scientific Reports*, 6, 30879, <https://doi.org/10.1038/srep30879> <https://www.nature.com/articles/srep30879#supplementary-information>, 2016.
- Brace, W. and Byerlee, J.: Stick-slip as a mechanism for earthquakes, *Science*, 153, 990–992, 1966.
- Braeck, S. and Podladchikov, Y. Y.: Spontaneous Thermal Runaway as an Ultimate Failure Mechanism of Materials, *Phys. Rev. Lett.*, 98, 095504, <https://doi.org/10.1103/PhysRevLett.98.095504>, 2007.
- 1265 Brechet, Y. and Estrin, Y.: Pseudo-portevin-le châtelier effect in ordered alloys, *Scripta Materialia*, 35, 217–223, [https://doi.org/10.1016/1359-6462\(96\)00126-1](https://doi.org/10.1016/1359-6462(96)00126-1), 1996.
- Buades, A., Coll, B., and Morel, J. M.: A Review of Image Denoising Algorithms, with a New One, *Multiscale Modeling & Simulation*, 4, 490–530, <https://doi.org/10.1137/040616024>, 2005.
- 1270 Cartwright, J. H. E., Hernández-García, E., and Piro, O.: Burrige-Knopoff Models as Elastic Excitable Media, *Phys. Rev. Lett.*, 79, 527–530, <https://doi.org/10.1103/PhysRevLett.79.527>, 1997.
- Cavaleri, L., Barbariol, F., Benetazzo, A., Bertotti, L., Bidlot, J.-R., Janssen, P., and Wedi, N.: The Draupner wave: A fresh look and the emerging view, *Journal of Geophysical Research: Oceans*, 121, 6061–6075, <https://doi.org/10.1002/2016JC011649>, 2016.
- Chen, X., Roshan, H., Lv, A., Hu, M., and Regenauer-Lieb, K.: The dynamic evolution of compaction bands in highly porous carbonates: The role of local heterogeneity for nucleation and propagation, *Progress in Earth and Planetary Sciences*, (in press), 2020.
- 1275

- Chester, F. M., Rowe, C., Ujiie, K., Kirkpatrick, J., Regalla, C., Remitti, F., Moore, J. C., Toy, V., Wolfson-Schwehr, M., Bose, S., Kameda, J., Mori, J. J., Brodsky, E. E., Eguchi, N., Toczko, S., 343, E., and Scientists, T.: Structure and Composition of the Plate-Boundary Slip Zone for the 2011 Tohoku-Oki Earthquake, *Science*, 342, 1208–1211, <https://doi.org/10.1126/science.1243719>, 2013.
- 1280 Clavijo, S. P., Sarmiento, A. F., Espath, L. F. R., Dalcin, L., Cortes, A. M. A., and Calo, V. M.: Reactive n-species Cahn–Hilliard system: A thermodynamically-consistent model for reversible chemical reactions, *Journal of Computational and Applied Mathematics*, 350, 143–154, <https://doi.org/10.1016/j.cam.2018.10.007>, 2019.
- Coleman, B. D. and Gurtin, M. E.: Thermodynamics and the Velocity of General Acceleration Waves, in: *Wave Propagation in Dissipative Materials*, edited by Coleman, B. D., Gurtin, M. E., Herrera R, I., and Truesdell, C., pp. 83–104, Springer Berlin Heidelberg, 1965.
- Collins, I. F. and Houlsby, G. T.: Application of thermomechanical principles to the modelling of geotechnical materials, *Proceedings - Royal Society of London, A*, 453 1964, 1975–2001, 1997.
- 1285 Cottrell, J. A., Hughes, T. J., and Bazilevs, Y.: *Isogeometric analysis: toward integration of CAD and FEA*, John Wiley & Sons, 2009.
- Crampin, S. and Gao, Y.: The New Geophysics, *Terra Nova*, 25, 173–180, <https://doi.org/10.1111/ter.12030>, 2013.
- Crampin, S. and Gao, Y.: The physics underlying Gutenberg–Richter in the earth and in the moon, *Journal of Earth Science*, 26, 134–139, <https://doi.org/10.1007/s12583-015-0513-3>, 2015.
- 1290 Crank, J.: *The mathematics of diffusion / by J. Crank*, Oxford science publications., Clarendon Press, Oxford [England], 1975.
- Dalcin, L., Collier, N., Vignal, P., Côrtes, A., and Calo, V. M.: PetIGA: A framework for high-performance isogeometric analysis, *Computer Methods in Applied Mechanics and Engineering*, 308, 151–181, 2016.
- Dematteis, G., Grafke, T., Onorato, M., and Vanden-Eijnden, E.: Experimental Evidence of Hydrodynamic Instantons: The Universal Route to Rogue Waves, *Phys. Rev. X*, 9, 041 057, <https://doi.org/10.1103/PhysRevX.9.041057>, 2019.
- 1295 Di Giacomo, D., Engdahl, E. R., and Storchak, D. A.: The ISC-GEM Earthquake Catalogue (1904–2014): status after the Extension Project, *Earth Syst. Sci. Data*, 10, 1877–1899, <https://doi.org/10.5194/essd-10-1877-2018>, 2018.
- Dieterich, J.: Time-dependent friction in rocks., *J. Geophys. Res.*, 377, 3690–3697, 1972.
- Dieterich, J.: Constitutive properties of faults with simulated gouge, in *Mechanical Behavior of Crustal Rocks*, *Geophys. Monogr. Ser.*, vol 24, edited by N. L. Carter et al., <https://doi.org/10.1029/GM024p0103>, 1987.
- 1300 Dudley, J. M., Genty, G., Mussot, A., Chabchoub, A., and Dias, F.: Rogue waves and analogies in optics and oceanography, *Nature Reviews Physics*, 1, 675–689, <https://doi.org/10.1038/s42254-019-0100-0>, <https://doi.org/10.1038/s42254-019-0100-0>, 2019.
- Durrleman, S., Boschetti, F., Ord, A., and Regener-Lieb, K.: Automatic detection of particle aggregation in particle code simulations of rock deformation, *Geochemistry, Geophysics, Geosystems*, 7, <https://doi.org/10.1029/2005GC001063>, 2006.
- Eberhard, M., Savojardo, A., Maruta, A., and Römer, R. A.: Rogue wave generation by inelastic quasi-soliton collisions in optical fibres, *Optics Express*, 25, 28 086, <https://doi.org/10.1364/OE.25.028086>, 2017a.
- 1305 Eberhard, M., Savojardo, A., Maruta, A., and Römer, R. A.: Rogue wave generation by inelastic quasi-soliton collisions in optical fibres, *Optics Express*, 25, 28 086, <https://doi.org/10.1364/oe.25.028086>, 2017b.
- Einav, I. and Guillard, F.: Tracking time with ricequakes in partially soaked brittle porous media, *Science Advances*, 4, eaat6961, <https://doi.org/10.1126/sciadv.aat6961>, 2018.
- 1310 Elphick, K. E., Sloss, C. R., Regener-Lieb, K., and Schrank, C. E.: Distribution, microphysical properties, and tectonic controls of deformation bands in the Miocene subduction wedge (Whakataki Formation) of the Hikurangi subduction zone, *Solid Earth*, 12, 141–170, <https://doi.org/10.5194/se-12-141-2021>, 2021.

- Español, P. and Warren, P. B.: Perspective: Dissipative particle dynamics, *The Journal of Chemical Physics*, 146, 150901, <https://doi.org/10.1063/1.4979514>, 2017.
- 1315 Estrin, Y. and Kubin, L.: *Spatial Coupling and Propagative Plastic Instabilities*, vol. 1, pp. 395–450, John Wiley and Sons, United States, 1995.
- Evans, D. and Searle, D.: The fluctuation theorem, *Advances in Physics*, 51, 1529 – 1585, 2002.
- Fan, X. and Lin, M.: Multiscale multifractal detrended fluctuation analysis of earthquake magnitude series of Southern California, *Physica A: Statistical Mechanics and its Applications*, 479, 225–235, <https://doi.org/10.1016/j.physa.2017.03.003>, 2017.
- 1320 Fisher, R. A.: The wave of advance of advantageous genes, *Annals of Eugenics*, 7, 355–369, <https://doi.org/10.1111/j.1469-1809.1937.tb02153.x>, 1937.
- Fitzgerald, B. W., Zarghami, A., Mahajan, V. V., Sanjeevi, S. K. P., Mema, I., Verma, V., El Hasadi, Y. M. F., and Padding, J. T.: Multiscale simulation of elongated particles in fluidised beds, *Chemical Engineering Science: X*, 2, 100019, <https://doi.org/10.1016/j.cesx.2019.100019>, 2019.
- 1325 Flake, G. W.: *The computational beauty of nature : computer explorations of fractals, chaos, complex systems, and adaptation*, Cambridge, Mass : MIT Press, Cambridge, Mass, 1998.
- Gomberg, J.: Slow slip phenomena in Cascadia from 2007 and beyond: a review, *GSA Bulletin*, 122, 963–978, <https://doi.org/10.1130/B30287.1>, 2010.
- Grigoli, F., Cesca, S., Rinaldi, A. P., Manconi, A., López-Comino, J. A., Clinton, J. F., Westaway, R., Cauzzi, C., Dahm, T., and
1330 Wiemer, S.: The November 2017 5.5 Pohang earthquake: A possible case of induced seismicity in South Korea, *Science*, 360, 1003, <https://doi.org/10.1126/science.aat2010>, 2018.
- Gu, J., Rice, J. R., Ruina, A. L., and Tse, S. T.: Slip Motion and Stability of a Single Degree of Freedom Elastic System with Rate and State Dependent Friction, *J.Mech.Phys.Solids*, 32, 167–196, 1984.
- Guillard, F., Golshan, P., Shen, L., Valdes, J. R., and Einav, I.: Dynamic patterns of compaction in brittle porous media, *Nature Physics*, 11,
1335 835–838, 2015.
- Hanasoge, S., Agarwal, U., Tandon, K., and Koelman, J. M. V. A.: Renormalization group theory outperforms other approaches in statistical comparison between upscaling techniques for porous media, *Phys. Rev. E*, 96, 033313, <https://doi.org/10.1103/PhysRevE.96.033313>, 2017.
- Hobbs, B. and Ord, A.: *Structural Geology: The Mechanics of Deforming Metamorphic Rocks*, Elsevier, Oxford,
1340 <https://doi.org/http://dx.doi.org/10.1016/B978-0-12-407820-8.00015-1>, 2015.
- Hobbs, B., Ord, A., and Regenauer-Lieb, K.: The Thermodynamics of deformed metamorphic rocks: A Review, *Journal of Structural Geology*, 33, 758–818, 2011.
- Hu, M., Veveakis, M., Poulet, T., and Regenauer-Lieb, K.: The Role of Temperature in Shear Instability and Bifurcation of Internally Pressurized Deep Boreholes, *Rock Mechanics and Rock Engineering*, 50, 3003–3017, <https://doi.org/10.1007/s00603-017-1291-2>, 2017.
- 1345 Hu, M., Schrank, C., and Regenauer-Lieb, K.: Cross-diffusion waves in hydro-poro-mechanics, *Journal of the Mechanics and Physics of Solids*, 135, 103632, <https://doi.org/10.1016/j.jmps.2019.05.015>, 2020.
- Jacquey, A. and Regenauer-Lieb, K.: Thermomechanics for geological, civil engineering and geodynamic applications, *Solid Earth*, Geoproc Conference 2019, submitted, 2020.
- Kanamori, H. and Brodsky, E. E.: The physics of earthquakes, *Physics Today*, 54, 34–40, 2001.

- 1350 Kanamori, H., Anderson, D. L., and Heaton, T. H.: Frictional melting during the rupture of the 1994 Bolivian earthquake, *Science*, 279, 839–842, 1998.
- Kettler, R. M., Loope, D. B., Weber, K. A., and Niles, P. B.: Life and Liesegang: Outcrop-Scale Microbially Induced Diagenetic Structures and Geochemical Self-Organization Phenomena Produced by Oxidation of Reduced Iron, *Astrobiology*, 15, 616–636, <https://doi.org/10.1089/ast.2015.1305>, 2015.
- 1355 Kichenassamy, S.: The Perona–Malik Paradox, *SIAM Journal on Applied Mathematics*, 57, 1328–1342, <https://doi.org/10.1137/S003613999529558X>, 1997.
- Kohlstedt, D. and Holtzman, B.: Shearing Melt out of the Earth: An Experimentalist’s Perspective on the Influence of Deformation on Melt Extraction, *Annual Reviews Earth and Planetary Sciences*, 37, 561–593, <https://doi.org/10.1146/annurev.earth.031208.100104>, 2009.
- Kolmogorov, A., Petrovsky, I., and Piskunov, N.: Etude de l’equation de la diffusion avec croissance de la quantite de matiere et son application a un probleme biologique, *Bulletin Universite de Etat a Moscow*, 1, 1–26, 1937.
- 1360 Kondepudi, D. and Prigogine, I.: *Modern Thermodynamics: From Heat Engines to Dissipative Structures*, John Wiley and Sons, Chichester, 1998.
- Koronovsky, N. V., Zakharov, V. S., and Naimark, A. A.: Short-Term Earthquake Prediction: Reality, Research Promise, or a Phantom Project?, *Moscow University Geology Bulletin*, 74, 333–341, <https://doi.org/10.3103/S0145875219040057>, <https://doi.org/10.3103/S0145875219040057>, 2019.
- 1365 L’Heureux, I.: Self-organized rhythmic patterns in geochemical systems, *Philosophical Transactions of the Royal Society A: Mathematical, Physical and Engineering Sciences*, 371, 20120356, <https://doi.org/10.1098/rsta.2012.0356>, 2013.
- Liesegang, R. E.: Eine scheinbar chemische Fernwirkung, *Annalen der Physik*, 324, 395–406, <https://doi.org/10.1002/andp.19063240210>, 1906.
- 1370 Lotka, A. J.: Analytical Note on Certain Rhythmic Relations in Organic Systems, *Proceedings of the National Academy of Sciences*, 6, 410, <https://doi.org/10.1073/pnas.6.7.410>, 1920.
- Luther, R.: Propagation of chemical reactions in space, *Journal of Chemical Education*, 64, 740, <https://doi.org/10.1021/ed064p740>, 1987.
- Lyakhovsky, V., Zhu, W., and Shalev, E.: Visco-poroelastic damage model for brittle-ductile failure of porous rocks, *Journal of Geophysical Research: Solid Earth*, 120, 2179–2199, <https://doi.org/10.1002/2014JB011805>, 2015.
- 1375 Manning, J. R.: Cross terms in the thermodynamic diffusion equations for multicomponent alloys, *Metallurgical and Materials Transactions B*, 1, 499–505, <https://doi.org/10.1007/BF02811561>, 1970.
- Masuda, T., Akimoto, A. M., and Yoshida, R.: 5.1 - Self-Oscillating Polymer Materials, pp. 219–236, William Andrew Publishing, <https://doi.org/10.1016/B978-0-323-37127-8.00013-3>, 2016.
- Mathematica: 2020.
- 1380 Maugin, G. and Muschik, W.: Thermodynamics with internal variables, vol. Volume 27 of *World Scientific Series on Nonlinear Science Series A*, pp. 77–105, WORLD SCIENTIFIC, https://doi.org/doi:10.1142/9789812796271_0004 [10.1142/9789812796271_0004](https://doi.org/doi:10.1142/9789812796271_0004), 1999.
- Molotkov, I. A. and Vakulenko, S. A.: Autowave propagation for general reaction diffusion systems, *Wave Motion*, 17, 255–266, [https://doi.org/10.1016/0165-2125\(93\)90005-Z](https://doi.org/10.1016/0165-2125(93)90005-Z), 1993.
- Monneau, R. and Patrizi, S.: Homogenization of the Peierls–Nabarro model for dislocation dynamics, *Journal of Differential Equations*, 253, 2064–2105, <https://doi.org/10.1016/j.jde.2012.06.019>, 2012.
- 1385 Nabika, H., Itatani, M., and Lagzi, I.: Pattern Formation in Precipitation Reactions: The Liesegang Phenomenon, *Langmuir*, 36, 481–497, <https://doi.org/10.1021/acs.langmuir.9b03018>, 2020.

- Obara, K.: Nonvolcanic deep tremor associated with subduction in southwest Japan, *Science*, 296, 1679–1681, 2002.
- 1390 Oberst, S., Niven, R. K., Lester, D. R., Ord, A., Hobbs, B., and Hoffmann, N.: Detection of unstable periodic orbits in mineralising geological systems, *Chaos: An Interdisciplinary Journal of Nonlinear Science*, 28, 085 711, <https://doi.org/10.1063/1.5024134>, 2018.
- Oettinger, H. C.: *Beyond Equilibrium Thermodynamics*, Hoboken : Wiley, Hoboken, 1st ed. edn., 2005.
- Ogawa, M.: Shear instability in a viscoelastic material as the cause of deep focus earthquakes, *Journal of Geophysical Research*, 92, 13 801–13 810, 1987.
- 1395 Ohnaka, M.: A constitutive scaling law and a unified comprehension for frictional slip failure, shear fracture of intact rock, and earthquake rupture, *Journal of Geophysical Research: Solid Earth*, 108, <https://doi.org/10.1029/2000JB000123>, 2003.
- Ohtani, M., Kame, N., and Nakatani, M.: Synchronization of megathrust earthquakes to periodic slow slip events in a single-degree-of-freedom spring-slider model, *Scientific Reports*, 9, 8285, <https://doi.org/10.1038/s41598-019-44684-4>, <https://doi.org/10.1038/s41598-019-44684-4>, 2019.
- 1400 Ord, A., Hunt, G. W., and Hobbs, B. E.: Patterns in our planet: defining new concepts for the application of multi-scale non-equilibrium thermodynamics to Earth-system science, *Philosophical Transactions of the Royal Society A: Mathematical, Physical and Engineering Sciences*, 368, 3–8, <https://doi.org/10.1098/rsta.2009.0217>, 2010.
- Orowan, E.: Mechanism of seismic faulting, pp. 323–346, *The Geological Society of America Memoir*, Washington, 1960.
- Ostoja-Starzewski, M.: *Microstructural Randomness and Scaling in Mechanics of Materials*, Chapman &Hall/CRC, London New York, 2008.
- 1405 Ostrovskii, L. A.: *Asymptotic perturbation theory of waves*, London, England : Imperial College Press, London, England Singapore, 2015.
- Paschotta, R.: *Quasi-Soliton pulses*, Wiley-VCH, 1st edition october 2008 edn., 2008.
- Peregrine, D. H.: Water waves, nonlinear Schrödinger equations and their solutions, *The Journal of the Australian Mathematical Society. Series B. Applied Mathematics*, 25, 16–43, <https://doi.org/10.1017/S0334270000003891>, 1983.
- Perzyna, P.: Fundamental problems in viscoplasticity., *Adv. Appl. Mech.*, 9, 243–377, 1966.
- 1410 Poulet, T., Veveakis, E., Herwegh, M., Buckingham, T., and Regenauer-Lieb, K.: Modeling episodic fluid-release events in the ductile carbonates of the Glarus thrust, *Geophysical Research Letters*, 41, 7121–7128, 2014a.
- Poulet, T., Veveakis, E., Regenauer-Lieb, K., and Yuen, D. A.: Thermo-poro-mechanics of chemically active creeping faults: 3. The role of serpentinite in episodic tremor and slip sequences, and transition to chaos, *Journal of Geophysical Research. Solid Earth*, 119, 4606–4625, <https://doi.org/10.1002/2014JB011004>, 2014b.
- 1415 Regenauer-Lieb, K. and Yuen, D. A.: Rapid conversion of elastic energy into plastic shear heating during incipient necking of the lithosphere, *Geophysical Research Letters*, 25, 2737–2740, 1998.
- Regenauer-Lieb, K., Veveakis, M., Poulet, T., Wellmann, F., Karrech, A., Liu, J., Hauser, J., Schrank, C., Gaede, O., and Fousseis, F.: Multiscale coupling and multiphysics approaches in earth sciences: Applications, *Journal of Coupled Systems and Multiscale Dynamics*, 1, 2330–152X/2013/001/042, <https://doi.org/10.1166/jcsmd.2013.1021>, 2013a.
- 1420 Regenauer-Lieb, K., Veveakis, M., Poulet, T., Wellmann, F., Karrech, A., Liu, J., Hauser, J., Schrank, C., Gaede, O., and Trefry, M.: Multiscale coupling and multiphysics approaches in Earth sciences: theory, *J. Coupled Syst. Multiscale Dyn*, 1, 2330–152X, <https://doi.org/10.1166/jcsmd.2013.1012>, 2013b.
- Regenauer-Lieb, K., Hu, M., Schrank, C., Chen, X., Clavijo, S. P., Kelka, U., Karrech, A., Gaede, O., Blach, T., Roshan, H., and Jacquey, A. B.: Cross-diffusion waves resulting from multiscale, multi-physics instabilities: theory, *Solid Earth*, 12, 869–883, <https://doi.org/10.5194/se-12-869-2021>, 2021.
- 1425

- Rice, J. R.: Heating and weakening of faults during earthquake slip, *J. Geophys. Res.*, 111, B05311, <https://doi.org/10.1029/2005JB004006>, 2006.
- Rice, J. R., Lapusta, N., and Ranjith, K.: Rate and state dependent friction and the stability of sliding between elastically deformable solids, *Journal of the Mechanics and Physics of Solids*, 49, 1865–1898, 2001.
- 1430 Rubinstein, J. and Sternberg, P.: Nonlocal reaction—diffusion equations and nucleation, *IMA Journal of Applied Mathematics*, 48, 249–264, <https://doi.org/10.1093/imamat/48.3.249>, 1992.
- Rudnicki, J. and Rice, J.: Conditions for the localization of deformation in pressure sensitive dilatant materials., *J. Mech. Phys. Solids*, 23, 371–394, 1975.
- Ruina, A.: Slip instability and state variable friction laws., *J. Geophys. Res.*, 88, 10 359–10 370, 1983.
- 1435 Scheel, A.: Spinodal Decomposition and Coarsening Fronts in the Cahn–Hilliard Equation, *Journal of Dynamics and Differential Equations*, 29, 431–464, <https://doi.org/10.1007/s10884-015-9491-5>, 2017.
- Schrank, C. E., Gioseffi, K., Blach, T., Gaede, O., Hawley, A., Milsch, H., Regenauer-Lieb, K., and Radlinski, A. P.: Tracking metamorphic dehydration reactions in real time with transmission small- and wide-angle synchrotron X-ray scattering: the case of gypsum dehydration, *Journal of Petrology*, <https://doi.org/10.1093/petrology/egaa041>, 2020.
- 1440 Schulz, S. E. and Evans, J. P.: Mesoscopic structure of the Punchbowl Fault, Southern California and the geologic and geophysical structure of active strike-slip faults, *Journal of Structural Geology*, 22, 913–930, [https://doi.org/10.1016/S0191-8141\(00\)00019-5](https://doi.org/10.1016/S0191-8141(00)00019-5), 2000.
- Sethna, J. P.: Order parameters, broken symmetry, and topology, pp. 243–288, Addison-Wesley Publishing Company, New York, 1992.
- Sethna, J. P.: *Statistical mechanics : entropy, order parameters, and complexity*, Oxford ; New York : Oxford University Press, <http://public.eblib.com/choice/publicfullrecord.aspx?p=422735>, formerly CIP, 2006.
- 1445 Sethna, J. P., Dahmen, K. A., and Myers, C. R.: Crackling noise, *Nature*, 410, 242–250, 2001.
- Shaar, M. and Ghavanloo, E.: Nonlocal Mechanics in the Framework of the General Nonlocal Theory, vol. 1 of *Springer Tracts in Mechanical Engineering*, pp. 95–122, Springer, Zurich, https://doi.org/https://doi.org/10.1007/978-3-030-63050-8_3, 2021.
- Showalter, K. and Tyson, J. J.: Luther’s 1906 discovery and analysis of chemical waves, *Journal of Chemical Education*, 64, 742, <https://doi.org/10.1021/ed064p742>, 1987.
- 1450 Shrira, V. I. and Geogjaev, V. V.: What makes the Peregrine soliton so special as a prototype of freak waves?, *Journal of Engineering Mathematics*, 67, 11–22, <https://doi.org/10.1007/s10665-009-9347-2>, <https://doi.org/10.1007/s10665-009-9347-2>, 2010.
- Solli, D. R., Ropers, C., Koonath, P., and Jalali, B.: Optical rogue waves, *Nature*, 450, 1054, <https://doi.org/10.1038/nature06402>, <https://doi.org/10.1038/nature06402>, 2007.
- Sornette, D.: Earthquakes: from chemical alteration to mechanical rupture, *Physics Reports-Review Section Of Physics Letters*, 313, 238–291, 1999.
- 1455 Sornette, D. and Ouillon, G.: Multifractal scaling of thermally activated rupture processes, *Physical Review Letters*, 94, art. no.–038 501, 2005.
- Sornette, D. and Pisarenko, V.: Fractal plate tectonics, *Geophysical Research Letters*, 30, 2003.
- Stanley, H. E. and Meakin, P.: Multifractal phenomena in physics and chemistry, *Nature*, 335, 405–409, <https://doi.org/10.1038/335405a0>, 1988.
- 1460 Storchak, D. A., Di Giacomo, D., Bondára, I., Engdahl, E. R., Harris, J., Lee, W. H. K., Villaseñor, A., and Bormann, P.: Public release of the ISC-GEM Global Instrumental Earthquake Catalogue (1900-2009), *Seismological Research Letters*, 84, 810–815, <https://doi.org/10.1785/0220130034>, 2013.

- 1465 Storchak, D. A., Di Giacomo, D., Engdahl, E. R., Harris, J., Bondár, I., Lee, W. H. K., Bormann, P., and Villaseñor, A.: The ISC-GEM Global Instrumental Earthquake Catalogue (1900–2009): Introduction, *Physics of the Earth and Planetary Interiors*, 239, 48–63, <https://doi.org/10.1016/j.pepi.2014.06.009>, 2015.
- Sun, Q., Hu, M., Schrank, C., and Regenauer-Lieb, K.: Reaction-diffusion waves in hydro-mechanically coupled porous solids, *GRL*, submitted, 2021.
- 1470 Towers, I. and Jovanoski, Z.: Application of rational Chebyshev polynomials to optical problems, *ANZIAM Journal*; Vol 50 (2008), <https://doi.org/10.21914/anziamj.v50i0.1396>, 2008.
- Tse, S. T. and Rice, J. R.: Crustal Earthquake Instability in Relation to the Depth Variation of Frictional Slip Properties, *Journal of Geophysical Research-Solid Earth and Planets*, 91, 9452–9472, 1986.
- Tsyganov, M. A. and Biktashev, V. N.: Classification of wave regimes in excitable systems with linear cross diffusion, *Phys. Rev. E*, 90, 062 912, <https://doi.org/10.1103/PhysRevE.90.062912>, 2014.
- 1475 Tsyganov, M. A., Biktashev, V. N., Brindley, J., Holden, A. V., and Genrikh, R. I.: Waves in systems with cross-diffusion as a new class of nonlinear waves, *Physics-Uspexhi*, 50, 263, 2007.
- Turiel, A., Pérez-Vicente, C. J., and Grazzini, J.: Numerical methods for the estimation of multifractal singularity spectra on sampled data: A comparative study, *Journal of Computational Physics*, 216, 362–390, <https://doi.org/10.1016/j.jcp.2005.12.004>, 2006.
- 1480 Turing, Alan, M.: The chemical basis of morphogenesis, *Philosophical Transactions of the Royal Society of London. Series B, Biological Sciences*, 237, 37–72, <https://doi.org/10.1098/rstb.1952.0012>, 1952.
- Ulmer, W.: Inverse problem of linear combinations of Gaussian convolution kernels (deconvolution) and some applications to proton/photon dosimetry and image processing, *Inverse Problems*, 26, 085 002, <https://doi.org/10.1088/0266-5611/26/8/085002>, 2010.
- Valero, G. and Moyano, A.: Chapter 13 - Searching for Spontaneous Mirror-Symmetry Breaking in Organoautocatalytic Reactions, pp. 241–258, Academic Press, <https://doi.org/10.1016/B978-0-12-812824-4.00013-7>, 2017.
- 1485 Vanag, V. K. and Epstein, I. R.: Cross-diffusion and pattern formation in reaction–diffusion systems, *Physical Chemistry Chemical Physics*, 11, 897–912, <https://doi.org/10.1039/B813825G>, 2009.
- Vardoulakis, I.: Thermo-poro-mechanics of rapid fault shearing, pp. 63–74, Springer Berlin Heidelberg, Berlin, Heidelberg, https://doi.org/10.1007/3-540-44424-6_5, 2001.
- 1490 Vasil'ev, V. A.: Autowave processes in distributed kinetic systems, *Soviet Physics Uspekhi*, 22, 615–639, <https://doi.org/10.1070/PU1979v022n08ABEH005591>, 1979.
- Vermilye, J. and Scholz, C.: The process zone: A microstructural view of fault growth, *Journal of Geophysical Research*, 1031, 12223–12 238, <https://doi.org/10.1029/98JB00957>, 1998.
- Veveakis, E. and Regenauer-Lieb, K.: Cnoidal waves in solids, *Journal of the Mechanics and Physics of Solids*, 78, 231–248, 2015.
- 1495 Veveakis, E., Poulet, T., and Alevizos, S.: Thermo-poro-mechanics of chemically active creeping faults: 2. Transient considerations, *Journal of Geophysical Research: Solid Earth*, 119, 4583–4605, <https://doi.org/10.1002/2013JB010071>, 2014.
- Wang, J., Cheng, X. P., Zeng, Y., Zhang, Y.-X., and Ge, N.-Y.: Quasi-soliton solution of Korteweg-de Vries equation and its application in ion acoustic waves, *Acta Physica Sinica*, 67, 110 201, <https://doi.org/10.7498/aps.67.20180094>, 2018.
- Wang, Y. and Merino, E.: Origin of fibrosity and banding in agates from flood basalts, *American Journal of Science*, 295, 49–77, <https://doi.org/10.2475/ajs.295.1.49>, 1995.
- 1500 Wang, Y., Xu, H., Merino, E., and Konishi, H.: Generation of banded iron formations by internal dynamics and leaching of oceanic crust, *Nature Geoscience*, 2, 781–784, <https://doi.org/10.1038/ngeo652>, 2009.

- Ward, C. B., Kevrekidis, P. G., and Whitaker, N.: Evaluating the robustness of rogue waves under perturbations, *Physics Letters A*, 383, 2584–2588, <https://doi.org/https://doi.org/10.1016/j.physleta.2019.05.030>, 2019.
- 1505 Wiemer, S. and Wyss, M.: Mapping the frequency-magnitude distribution in asperities: An improved technique to calculate recurrence times?, *Journal of Geophysical Research-Solid Earth*, 102, 15 115–15 128, 1997.
- Yang, J.: *Nonlinear Waves in Integrable and Non-integrable Systems*, Society for Industrial and Applied Mathematics, 2010.
- Zaiser, M. and Hähner, P.: Oscillatory Modes of Plastic Deformation: Theoretical Concepts, *physica status solidi (b)*, 199, 267–330, [https://doi.org/10.1002/1521-3951\(199702\)199:2<267::AID-PSSB267>3.0.CO;2-Q](https://doi.org/10.1002/1521-3951(199702)199:2<267::AID-PSSB267>3.0.CO;2-Q), 1997.
- 1510 Zakharov, V., Dias, F., and Pushkarev, A.: One-dimensional wave turbulence, *Physics Reports*, 398, 1–65, <https://doi.org/10.1016/j.physrep.2004.04.002>, 2004.
- Zemskov, E. P., Tsyganov, M. A., and Horsthemke, W.: Oscillatory pulses and wave trains in a bistable reaction-diffusion system with cross diffusion, *Physical Review E*, 95, 012 203, <https://doi.org/10.1103/PhysRevE.95.012203>, 2017.
- Zuev, L. and Barannikova, S.: Plastic Flow Macrolocalization: Autowave and Quasi-Particle,, *Journal of Modern Physics*, 1, 1–8, <https://doi.org/10.4236/jmp.2010.11001>, 2010.